

IMPERIAL

Experimental and Computational Investigation of a Small-Scale Turbopump Featuring a Barske Impeller and a Supersonic Turbine



Student: Martin Leung
CID: 02217557
Academic Supervisor: Dr Aaron Knoll
Second Marker: Dr Roderick Lubbock
Department: Department of Aeronautics
Academic year: 2025/2026
Date: 2026/06/01

Department of Aeronautics
South Kensington Campus
Imperial College London
London SW7 2AZ
U.K.

Abstract

Your abstract goes here. Summarise the key motivations, methodology, and findings of your turbopump FYP.

Acknowledgements

Plan of everyone I need to thank, to be written into prose:

Dr. Aaron Knoll, for being my supervisor - Grounding me on my progress and helping me along all the way through admin and safety - Repeatedly told me where I actually was, like telling me to get an extension

Dr. Lubbock - Lending me the torquemeter

Mark Grant - Guiding me on mechanical design, allowing me to test in the hypersonic lab

Hackspace: Fred Holdsworth, David Miller, Mohammed Mehdi Nasr Esfhani - teaching me all about machining over the past 4 years, hundreds of hours of guidance and especially so in this project

Nigel - Guiding me on safety, working through and being patient with this project with a lot of risk and working through the incident report

David Wright - Lending me a lot of fittings from the thermofluids lab of mecheng

Franco - Lending me a lot of the electronics equipment, the box, safety relay, a lot of guidance on safety wiring

Xiao - Giving advice and teaching me about the magtrol system

Liam Donelly - Rocket turbine FYP who I borrowed a lot of knowledge and equipment from, guiding me on magtrol and the general direction of the project

Rui, Safee - Staying by my side as I test and occasionally even helping me set up and debug. Rui especially helped me solve many many problems

Aleks Kent - Starting the E-pump project in 2023 and inspiring me to get into turbomachinery, and being my best friend

Jordan Farrar, Mark Thornton, Ian Pardew, - For helping me 3d print and laser cut parts, general manufacturing

Roland Hutchins - Allowing me to borrow the garden pump

ICLR - Opportunity and where I learned everything Martin England, Elliot Brookes Gayton, Kiran de Silva - For bringing me into this world of rocketry, electronics and propulsion when I was a first year

Airborne engineering - where I learned a lot a lot of test rig and practical skills

Rudra Nakade - My great friend who I learned so much about doing rocketry with while working with him, and being a poweruser, who eventually convinced me to do a turbopump FYP out of my many rocketry interests

Babz and Raghav - Great mates at ICLR and also with the propulsion team, gave me fittings

Elsbeth Lau - My great friend who supported me during the harder times of this project

Mom and Dad - For supporting me all I life, sacrificing so much of their life to get me into imperial and supporting my life dream of being a rocket engineer, always being there for me and cheering me on

Mario - Guidance on pump design, and reading this posts on r/rocketry discord let me learn a lot

Oliver Esmond, Tim Barrett - allowing me to borrow ICSS equipment

Chris Noon - allowing me to use their swagelok valve and test rig equipment from turbomachinery lab

Tian - teaching me about mechanical from 2022 and being my great friend ever since

Contents

Acknowledgements	iii
List of Figures	vi
List of Tables	viii
Nomenclature	ix
1 Introduction	1
1.1 Small scale rocket pump challenges	1
1.2 Small scale rocket turbine challenges	2
1.3 Scope and Limitations	2
1.4 Aims and Objectives	2
1.5 Thesis Structure	2
2 Literature and Theory	2
2.1 Pump Theory	3
2.1.1 Euler Turbine Equation	3
2.1.2 Non-dimensional Performance and Scaling	3
2.1.3 Pump Scaling, Affinity Laws	3
2.1.4 Cavitation and NPSH	4
2.2 Main Loss Mechanisms at Low Specific Speed	4
2.2.1 Disc Friction Loss	4
2.2.2 Hydraulic Losses	5
2.3 The Barske Partial-Emission Pump	5
2.3.1 Barske Pump Performance	5
2.3.2 Barske Sizing Method	6
2.3.3 Efficiency and Disc Friction	6
2.3.4 Lock's Refined Model	7
2.4 Turbine Theory	7
2.4.1 Impulse Turbines	7
2.4.2 Impulse Turbine Efficiency	8
2.4.3 Impulse vs Reaction Turbines	8
2.4.4 Blade Height and Partial Admission	9
2.4.5 Loss Model	9
2.5 Turbine Blade Design	10
2.5.1 Method of Characteristics for Supersonic Impulse Blade Design	10
2.5.2 Flow Separation	11
2.5.3 Supersonic Starting	12
2.5.4 Surface Mach Number Selection	12
2.5.5 Finite Leading Edge	13
2.5.6 Nozzle Design	14
3 Design	14
3.1 Pump Design	15
3.1.1 Sizing	15
3.1.2 Diffuser	16
3.1.3 Mechanical Design	16
3.2 Turbine Design	17
3.2.1 Architecture Selection	17
3.2.2 Design Point and sizing	18
3.2.3 Blade Passage Design	19
3.2.4 Losses and Predicted Efficiency	19
3.2.5 Blade Geometry Details	19
3.2.6 Mechanical Design	19

4	Experimental Setup	20
4.1	Test Configurations	20
4.2	Mechanical Layout and Shaft Train	21
4.2.1	Shaft alignment	21
4.3	Water Circuit	21
4.3.1	Inlet and Outlet Throttle Valves	22
4.4	Air supply	22
4.5	Instrumentation and Data Acquisition	23
4.5.1	Main Architecture	23
4.5.2	Power Architecture and Custom Boards	23
4.5.3	Electronics Safety Design	24
4.5.4	ADC Measurements	24
4.5.5	Other sensors	24
4.5.6	Actuator Control	24
4.5.7	Cavitation Imaging	25
4.5.8	Instrument Uncertainty	25
4.5.9	Electric Motor Drive and Control	26
5	Results and Discussion	26
5.1	Experimental Campaign	26
5.2	Electric Motor Driven Pump Testing	26
5.3	Data Processing and Uncertainty	27
5.4	Pump Head-Flow Characteristics	29
5.5	Pump: Efficiency and Churning	30
5.6	Pump: Extrapolation to Design Speed	30
5.7	Pump: Cavitation	31
5.8	Pump: Video Observations of Cavitation	32
5.9	Coupled Turbopump	34
5.10	Extrapolation to the Design Point	36
5.11	Synthesis	36
6	Conclusions	37
6.1	Future Work	37
	References	39
A	Conventional Impeller Design Attempt	41
B	Supplementary Safety Calculations	41
B.1	Venting Noise	41
B.2	Venting Reaction Force	41
C	Additional Figures and Tables	41

List of Figures

1	Optimum pump geometry and attainable efficiency against specific speed. Adapted from Balje [1] with specific speed in n_q units.	1
2	Velocity triangles in a conventional pump, adapted from Gulich	3
3	Disc friction loss vs specific speed n_q after Gülich. At low specific speed the disc friction dominates.	4
4	Breakdown of pump losses against specific speed, after Gülich. At low specific speed the disc friction dominates while the impeller (blade) losses are small.	5
5	Comparison of the conventional and Barske pump architectures. The Barske impeller is open, has straight radial blades, and discharges into an annular casing with a single tangential diffuser.	5
6	Velocity triangles in a forced vortex pump	5
7	Impulse turbine velocity triangle nomenclature at the rotor inlet (station 3) and exit (station 4).	8
8	Comparison of efficiency between impulse and reaction turbines against u/c_3 and tip clearance.	9
9	Typical MOC blade terminology.	10
10	Goldman's published figures describing the distribution of Mach number and incompressible form factor H_i along the blade surfaces. [2]	11
11	Validation of Sasman and Cresci's method to compute the development of the compressible turbulent boundary layer against Goldman's published figures.	12
12	The effect of surface Mach number spread on the blade passage, for the same inlet conditions. A narrow spread produces thin passage where the boundary layers occupy a large fraction of the width, while a wide spread opens the passage up.	13
13	Finite leading edge treatments for supersonic blades: incidence angling of one surface, in passage shock cancellation, and the small wedge used to cancel the resulting compression shock.	14
14	Calculated efficiency of a conical nozzle as a function of area ratio from NASA SP-8120 [3]	14
15	The sized pump geometry drawn to scale. The meridional section (left) and plan view (right).	15
16	Labeled CAD isotropic and section view of the pump assembly	16
17	Geometric dimensions of an OD pressurized the mechanical seal by Karassik [4].	17
18	The turbine design space over mean diameter and mass flow, evaluated with the full sizing and loss model at the design speed. The panels show nozzle exit Mach number, blade height and predicted total to static efficiency. Overlaid lines are the design constraints (blade height ≥ 4 mm, nozzle throat ≥ 0.5 mm, $M_3 \leq 1.8$), the shaded region is infeasible, and the marker is the selected design point.	18
19	The ideal MoC countour and incompressible form factor H_i check for the design surface mach numbers $M_l = 1.05$ and $M_u = 1.5$	19
20	CAD Blade profile	19
21	Labeled CAD isotropic and section view of the turbine assembly	20
22	The three test configurations. In each case the TM306 torquemeter sits between the driving component and the load, so torque is measured at the shaft.	20
23	Shaft alignment procedure using the flat faces of the component mounts.	21
24	P&ID of the water circuit for the electric motor driven pump test configuration.	21
25	Servo driven throttle valve assembly	22
26	Extrapolated against measured valve capacity	22
27	P&ID of the water and air circuit for the turbopump configuration.	22
28	Block diagram of full electronics system including safety, data acquisition, and control components.	23
29	The electronics box with the Raspberry Pi, ESP32S3s and power supply.	23
30	The interior of the electronics box showing the ESP32S3s and perfboard.	24
31	Cavitation imaging arrangement	25
32	The electric motor and ESC mounted to the test rig.	26
33	Raw electric pump driven pump experimental data over 5 different motor throttle settings	28
34	Dimensional and non-dimensional head-flow curves, with two Lock model curves overlayed.	29
35	Pump efficiency and the churning measurement.	30
36	Peak overall efficiency per run against shaft speed, with the fitted loss ratio $(1 - \eta) \propto Re^{-a}$ and its uncertainty band extrapolated to the design speed. The fitted exponent $a = 0.098 \pm 0.010$ matches the textbook friction scaling.	31
37	Suction test curves at constant speed: normalised head against NPSH available, one curve per held flow rate, by successive reduction of the inlet pressure. The lines are smoothing splines fitted through them to show the trend. The horizontal line is the 3% head-drop criterion used for fig. 39.	32
38	Stills through the transparent front casing at descending NPSH. The eye cavitates first with no measurable head effect, while the appearance of throat cavitation coincides with the head breakdown. Frame timestamps are synchronised to the logged data.	33
39	NPSH at 3% head breakdown against flow rate, with the visually observed throat cavitation onsets and the Lock throat cutoff curve. Error bars as in fig. 34.	33

40	Coupled turbine driven pump operation against the motor driven characteristic curves. The coupled data, coloured by shaft speed, lands on the same head flow behaviour measured under motor drive. . .	34
41	Coupled shaft torque against speed: measured data, the started flow model (dashed) and the unstarted model with a reduced effective jet (solid with band). The factor of four deficit against the started model is explained by the rotor running unstarted below the starting threshold.	35
42	The pooled non dimensional characteristic carried to 20 000 rpm by the affinity laws, with the Lock model at design speed and the design point marked.	36

List of Tables

1	Turbopump system design point.	15
2	Pump design summary. The impeller dimensions are the sizing code output; the diffuser throat d_3 and exit d_4 are the as-built values, which depart from the sized values for the reasons given in the text. . .	16
3	Turbine design summary	18
4	Measurement channels, ranges and systematic uncertainties.	26
5	Predicted against measured summary. Percentage differences are computed by the analysis pipeline from the same registry that supplies every number in this thesis.	36

Nomenclature

a	Speed of sound (m/s)
A, A_{th}	Area; geometric nozzle throat area (m ²)
b	Turbine rotor blade height (mm)
b_1, b_2	Pump blade axial width at stations 1, 2 (mm)
b_c, h_c	Annular casing width, radial depth (mm)
c	Absolute velocity (m/s)
c_p	Specific heat at constant pressure (J/(kg K))
c_s	Spouting velocity (m/s)
C_H, h_0	Lock/Busemann head-correction constants (—)
$d_0 \dots d_4$	Pump station diameters (mm)
d_m	Turbine mean (pitch) diameter (mm)
E	Energy (J); Young's modulus in ?? (Pa)
f	Friction coefficient (—)
F_R	Radial thrust (N)
g	Gravitational acceleration (m/s ²)
H	Pump head (m)
H_{T2}	Lock's total impeller generated head (m)
H_{NL}	Nozzle loss head (m)
H_3	head at diffuser throat (m)
h	Specific enthalpy (J/kg); Δh_s isentropic drop
I	Second moment of area (m ⁴)
J	Mass moment of inertia (kg m ²)
k_d	Barske diffuser kinetic-recovery coefficient (—)
k_N, k_R	Nozzle, rotor velocity coefficients (Weiss) (—)
K_1	Lock's pre-rotation factor (—)
K_v	Valve flow coefficient (eq. (52))
M	Mach number; M_{w3} rotor-inlet relative Mach (—)
$\dot{m}$	Mass flow rate (kg/s)
n	Shaft speed (rpm)
n_q	Specific speed $n\sqrt{Q}/H^{0.75}$ (rpm, m ³ /s, m)
$\text{NPSH}_a, \text{NPSH}_3$	Available NPSH; NPSH at 3 % head drop (m)
p	Static pressure (Pa); p_{01}, T_{01} total state at station 1; p_v vapour pressure
Δp	Pump total pressure rise (Pa); Δp_{st} static component
P	Power (W); P_{RR} disc friction/churning; P_m mechanical loss; P_w ventilation (windage) power
Pr	Prandtl number (—)
q	Dynamic pressure $\frac{1}{2}\rho c^2$ (Pa)
Q	Volumetric flow rate (m ³ /s); Q_L leakage flow; Q_{opt} optimum-flow point
r	Radius (m); recovery factor in ?? only
R	Specific gas constant (J/(kg K))
Re_u	Peripheral Reynolds number $u_2 r_2 / \nu_l$ (—)
s_{ax}	Impeller-casing axial clearance (mm)
SG	Specific gravity (—)
T	Temperature (K)
u	Blade (peripheral) speed (m/s)
w	Relative velocity (m/s)
Y	Specific work (J/kg)
z	Blade count (—)
α	Absolute flow angle from circumferential (°)
β	Relative flow / blade angle from circumferential (°)
γ	Heat capacity ratio (—)
ζ	Degree of (partial) admission (—)
ζ_D	Diffuser-nozzle loss coefficient (—)
η	Efficiency: pump overall $\rho g Q H / (\tau \omega)$; η_h hydraulic; η_{ts} turbine total-to-static
μ	Dynamic viscosity (always with a state subscript); Mach angle within the MoC set only
ν	Prandtl–Meyer angle (°); kinematic viscosity is written μ/ρ or ν_l ; Poisson's ratio in ??
ρ	Density (kg/m ³); ρ_b blade material density
σ	Stress, with subscript (??); slip factor (Wiesner) in §2; standard deviation in the uncertainty analysis
τ	Shaft torque (N m); τ_{pc} polycarbonate shear strength in ??
ϕ	Pump flow coefficient $Q/(\pi d_2 b_2 u_2)$ (—)
ψ	Pump head coefficient $2gH/u_2^2$ (—)
ω	Shaft angular velocity (rad/s); $\dot{\omega}$ angular acceleration; ω_s nondimensional specific speed

Structural and instrumentation symbols (scoped to their sections)

B_r	Seal balance ratio (–)
M_b, y	Blade root bending moment (N m); extreme fibre distance (m)
V, V_{ref}, V_{exc}	Voltage; ADC reference and transducer excitation (V)
N	Sample count in oversampling, eq. (53) (–)
$\mathcal{V}$	Stored-gas / vessel volume (m ³)
s_p	Shear-plug perimeter, ?? (m)

Subscripts

$0 \dots 4$	Station index (machine-scoped, see below)
th, st	Theoretical; static
RR, m, h, ts	Disc friction (churning); mechanical / mean; hydraulic; total-to-static
opt, max	Optimum-flow point; maximum
aw, s, v, L	Adiabatic wall; isentropic; vapour; leakage

Superscripts and operators

$\square, \bar{\square}$	Time rate; mean / non-dimensionalised
$\square^*$	Critical (sonic) reference / non-dimensional (MoC set)
$\square^e$	Effective value, e.g. c_{3u}^e

Stations (machine-scoped)

Pump	0 suction/eye inlet · 1 blade leading edge · 2 blade tip · 3 diffuser throat · 4 discharge
Turbine	1 stator inlet plenum · 2 nozzle throat · 3 nozzle exit/rotor inlet · 4 rotor exit

Scoped symbol sets (declared here, used only in their subsections)

MoC set (section 2.5.1)	$M^* = c/a^*, a^* = \sqrt{\gamma RT^*}, r^*, R^*, x^*, y^*, \mu_k$ (Mach angle), $m_k, \Delta\nu$
Starting set (section 2.5.1)	M_l^*, M_u^* surface critical Machs; K_{max}^* weight-flow constant; Q vortex parameter; C 2D
Boundary layer set (Sasman–Cresci)	H_i shape factor, θ momentum thickness, $f, C_f, g_w, T_e, \bar{T}, s/c, \delta^*$ displacement thicken

Abbreviations

ADC	Analogue to Digital Converter
BEP	Best Efficiency Point
CFD	Computational Fluid Dynamics
DAQ	Data Acquisition
ESC	Electronic Speed Controller
FEA	Finite Element Analysis
GUI	Graphical User Interface
MoC	Method of Characteristics
P&ID	Piping and Instrumentation Diagram
SLA	Stereolithography (resin printing)

1 Introduction

Rocket engines require high pressures to operate efficiently. Small scale liquid propulsion such as satellite propulsion and amateur liquid rocket propulsion runs almost entirely on pressure fed feed systems due to their simplicity and reliability. Larger orbital rockets use turbopumps because the mass of the required tanks becomes prohibitive. However, as space launch becomes exponentially more accessible, there is a growing interest in small scale rocket propulsion systems. For example, lunar landers, satellite propulsion and amateur liquid rockets are seeing a resurgence in interest. Due to the historical focus on large turbopumps for such applications, turbopumps at the smaller scale are not as well documented and have different design considerations. A turbopump is a pump and the turbine that drives it, and both are punished by the small scale.

1.1 Small scale rocket pump challenges

Pump driven propulsion is the solution orbital liquid rockets use to solve the tank mass problem. By storing propellants at lower pressures and pumping them to the required pressures allows for a large reduction in tank mass. The pump is usually driven by turbines powered by burning a portion of the propellants, or by the heat generated by the cooling of the engine. In recent years, battery and electric pump technology has advanced to such a point that for smaller rockets such as the Electron rocket by Rocket Lab [?], electric pumps are starting to become a more viable alternative to turbine driven pumps.

Pumps are generally characterized by their flow rate Q , the head H and rotor speed n [?]. These three parameters largely decide the pump geometry and type of pump. These three parameters can be related by a quantity known as specific speed, n_q , N_s or ω_s depending on the units and definitions used:

$$n_q = \frac{n\sqrt{Q}}{H^{3/4}} \quad [\text{RPM}, \text{m}^3/\text{s}, \text{m}] \quad (1)$$

Different pump geometries are optimal for different regions of specific speed as can be shown by fig. 1. The radial centrifugal impeller reaches its best efficiency roughly between an n_q of 10 and 40 [5, ?], and rocket engine pumps are normally sized to sit in this band, splitting the head across multiple stages when a single stage would otherwise fall below it. This works great for large rocket engines, but scaling this down to smaller engines becomes increasingly difficult. All rocket engines require high pressures, but smaller rocket engines require less flow rate. To stay in the specific speed according to eq. (1) that allows for high efficiency in the centrifugal pump requires increasing rotational speed.

To achieve the specific speed n_q of 20 for a smaller rocket engine of around 5 kN requiring 1.0 kg/s of kerosene at 50 bar, eq. (1) leads to rotational speeds of around 71 051 rpm. Such high rotational speeds leads to challenging mechanical design conditions. To solve this problem, a single pump can be separated into multiple stages, separating the head rise to increase the specific speed of each stage. This is a common solution to pumping hydrogen. This thesis however addresses the other solution, to study a single stage pump geometry at this low specific speed. In rocket applications, the lower component efficiency could trade better by other factors such as lower mass, cost, reliability and simplicity.

As shown in fig. 1, at lower specific speeds, the partial emission pump, of which the Barske impeller is the main form, becomes the optimum efficiency pump geometry at specific speeds of 5-10. The term partial emission refers how the pump outlet only taps a small arc of the pump periphery. Full emission pumps are designed to have the impeller discharge around the whole annulus, collecting flow through a continuous volute. Literature uses the names partial emission and Barske interchangeably.

However, even though these pumps are the most efficient at these low specific speeds, they physically cannot achieve the high efficiencies of a full emission pump. This is the main limitation of trying to operate at low specific speeds. Due to its lower efficiency and the lack of pump fed liquid rockets for small engines, there is a lack of literature, design knowledge and experimental data surrounding these pumps. This thesis aims to address this gap by reviewing




Figure 1: Optimum pump geometry and attainable efficiency against specific speed. Adapted from Balje [1] with specific speed in n_q units.

existing literature, designing and manufacturing a partial emission centrifugal pump and comparing its experimental performance specifically in the use case of rocket engines.

The lack of data is specifically a lack of experimental data. Open studies of this regime do exist, but they are mostly numerical. A Barske type impeller at $n_q = 4.7$ was studied with CFD and reached an efficiency of 31.5% [6]. A conventional closed impeller was designed at the same specific speed as this thesis, but it was CFD only, unvalidated, and required closed channels of 0.31 mm width [7]. A partial emission rocket e-pump for a lunar lander was designed for 630 m at 40,000 RPM, again in CFD [8]. What is scarce is open experimental characterisation at this specific speed, with a measured loss breakdown and measured cavitation behaviour, and that is what this work supplies. A NASA trade study of low thrust rocket pumps covers the same trade and carries the Barske pump as a candidate [9].

1.2 Small scale rocket turbine challenges

On the other end of the turbopump shaft is the turbine which drives the pump. The turbine faces the same problem as the pump. If using the gas generator cycle, the small turbine leads to lower blade speeds u . To extract the maximum work from the gas, gas velocity c_s must be high, leading to a supersonic blade turbine. The high gas velocity relative to blade speed leads to the turbine running at a lower efficiency than the optimum $u/c_s \approx 0.5$ [?]. The smaller mass flow also cannot fill the annulus at a sensible blade height, leading to partial admission where only a fraction of the annulus has gas flowing through it at any given time. This makes the stage lossy and awkward to design. In addition to these design limitations, supersonic turbine design is far less studied than subsonic, where methods are scattered across older sources.

This thesis tackles the design of a turbopump in the context of small scale liquid rocket engines which forces both pump and turbine off optimum design conditions, then demonstrates their coupled performance in a full integration test. The thesis is framed around the design of a 20 000 rpm turbopump using water as an inert simulant for the pumped rocket propellants. Then, a supersonic partial admission impulse turbine is designed to drive the pump using compressed air as the working fluid. The two are then coupled together and tested as a single system to evaluate performance.

1.3 Scope and Limitations

This thesis covers the theory, design, manufacture and testing of a small scale turbopump system on inert propellants. The pump and turbine were tested up to 9000 rpm, significantly lower than the design speed of 20 000 rpm in the first and final iterations of the conducted experiments. This means the data validation can only happen for the off-design point and extrapolation to the design point is required. Cryogenic and hot gas design and testing are strictly outside the scope of this thesis. Operational safety procedures are included in the appendix.

1.4 Aims and Objectives

The aim of this thesis is to investigate the performance of a small scale rocket low specific speed turbopump with a Barske pump and a supersonic partial admission turbine. To this end, the objectives of this thesis are:

1. Pump: Assemble a Barske pump design methodology from the literature, use it to design and build the pump, then characterise it experimentally for head-flow, efficiency and cavitation, and compare the measurements against the methodology's predictions and prior literature.
2. Turbine: Assemble a design methodology for a single-stage partial-admission supersonic impulse turbine from the literature, use it to design and build the rotor, then validate those models against the achievable test data.
3. Turbopump: Couple the pump and turbine and demonstrate them running as a single machine, then use that result to check whether the combined methodology predicts a working turbopump of this class.

1.5 Thesis Structure

Chapter 2 establishes the theoretical background for both machines: the Barske pump and its sizing and loss models, and the supersonic impulse turbine theory including blade profile design and loss models. Chapter 3 applies these models to design the actual pump and turbine, including the mechanical and structural design. Chapter 4 describes the experimental setup: the test configurations, the water and air circuits, and the custom instrumentation and data acquisition system. Chapter 5 presents the experimental results and discusses them against the design predictions and prior literature. Chapter 6 draws conclusions against the objectives and recommends future work.

2 Literature and Theory

Much of the supersonic blading design methodology dates from the 1950s and 60s [10, 11]. The same analytical core, method of characteristics nozzle and blade passage design remains foundation of current work. Sudhof's 2020

dissertation [12] frames modern developments into design as a paradigm shift. Older methods studied analytical profiles first then checked practical restrictions such as finite leading edge thickness, shock boundary layer interaction afterwards. Modern computational capacity lets the blade be designed and optimised around these restrictions from the start. Griffin and Dorney demonstrated this on a two-stage supersonic turbine, where CFD, response-surface and neural-net optimisation of a conventionally designed baseline gave a measured total-to-static efficiency gain of 9 points [13]. These methods are still the basis of current small turbine design studies [14, 15]. On the pump side, the Barske architecture is seeing renewed interest [6], but literature is still very scarce [8].

2.1 Pump Theory

2.1.1 Euler Turbine Equation

The working principles for pump and turbine design can be derived from the conservation of angular momentum by Newton's second law of motion. In turbomachinery, this is usually expressed in terms of the Euler turbine equation shown in eq. (2), where c is velocity in the inertial frame, w is in the rotating frame and u is the local circumferential velocity as shown in fig. 2.

$$P = \tau\omega = \rho Q (r_2 c_{2u} - r_1 c_{1u}) \omega = \rho Q (u_2 c_{2u} - u_1 c_{1u}) \quad (2)$$

Rewriting this equation in terms of specific work $Y = P/\rho Q$ per unit mass:

$$Y = (r_2 c_{2u} - r_1 c_{1u}) \omega = u_2 c_{2u} - u_1 c_{1u} \quad (3)$$

derive from Bernoulli, with rotating frame substitution $c^2 = w^2 - u^2 + 2 \times u \times c_u$ and neglecting compressibility losses:

$$p_1 + \frac{\rho}{2} w_1^2 - \frac{\rho}{2} u_1^2 = p_2 + \frac{\rho}{2} w_2^2 - \frac{\rho}{2} u_2^2$$

and as such the theoretical rise in static pressure:

$$\Delta p_{st} = p_2 - p_1 = \frac{\rho}{2} (w_1^2 - w_2^2) + \frac{\rho}{2} (u_2^2 - u_1^2) \quad (4)$$

2.1.2 Non-dimensional Performance and Scaling

Understanding why low specific speed pumps are less efficient, and the design choices that follow from it, comes down to a few non-dimensional parameters so they are defined first. The following derivation uses velocity terms shown visually in fig. 2. A pump adds energy to the fluid by spinning it up towards the speed of the impeller rim, u_2 . The work it does per unit mass is the rim speed times the swirl velocity it adds to the fluid, $u_2 c_{2u}$, and that swirl is proportional to the rim speed, so the head a pump can generate scales with u_2^2 . The flow rate meanwhile leaves the impeller radially through the exit area $\pi d_2 b_2$ at the meridional velocity c_{m2} where b_2 is the blade width at the exit, so $Q = \pi d_2 b_2 c_{m2}$. Measuring the head against the rim-speed head u_2^2 , and the radial velocity against the rim speed u_2 , gives the head and flow coefficients, following Gülich [5]:

$$\psi = \frac{2gH}{u_2^2}, \quad \phi = \frac{c_{m2}}{u_2} = \frac{Q}{\pi d_2 b_2 u_2} \quad (5)$$

These two coefficients form the non-dimensional performance map of a pump, where the original pump curve $H = f(Q)$ is transformed into $\psi = f(\phi)$. For any geometrically similar pump with the same velocity triangles, the same $\psi(\phi)$ curve applies, so the performance of a small model can be scaled to a larger machine [5].

2.1.3 Pump Scaling, Affinity Laws

Using the non-dimensional pump characteristic curve $\psi = f(\phi)$, the performance of a pump can be scaled to different speeds and sizes. At a design flow rate, meaning a fixed ϕ , the head coefficient ψ is known. This is what makes them useful for scaling. At a fixed point on the $\psi(\phi)$ curve, eq. (5) can be rearranged:

$$H = \frac{\psi u_2^2}{2g}, \quad \Rightarrow \quad H \propto u_2^2 \propto n^2 d_2^2 \quad (6)$$

$$Q = \phi \pi d_2 b_2 u_2, \quad \Rightarrow \quad Q \propto u_2 d_2^2 \propto n d_2^3 \quad (7)$$




Figure 2: Velocity triangles in a conventional pump, adapted from Gülich

2.1.4 Cavitation and NPSH

Cavitation occurs when the local static pressure of the fluid drops below its vapour pressure, causing the liquid to boil into vapour bubbles. In a pump, this is highly undesirable as the bubbles form and collapse violently repeatedly, eroding the impeller and diffuser surfaces. Additionally, the vapour bubbles are compressible, so they absorb energy that would otherwise be delivered to the fluid, reducing the head and efficiency of the pump. The cavitation behaviour of a pump is characterised by the net positive suction head, NPSH. There are different types of NPSH. At the supply side, NPSH_a stands for net positive suction head available, which is the head margin above vapour pressure at the pump inlet. On the pump side, a NPSH_r is usually specified. Standing for net positive suction head required, it is the minimum NPSH_a at which the pump can operate without cavitation. The standard performance criterion is NPSH_3 , the available NPSH at which the developed head has dropped 3% below its fully wetted value at constant speed and flow [5]. The formula for the general NPSH is given in eq. (8), where p_{in} is the inlet static pressure, p_{vap} is the vapour pressure of the fluid, ρ is the fluid density, g is gravitational acceleration and v_{in} is the inlet velocity.

$$\text{NPSH} = \frac{p_{in} - p_{vap}}{\rho g} + \frac{v_{in}^2}{2g} \quad (8)$$

2.2 Main Loss Mechanisms at Low Specific Speed

Losses in pumps can be separated into power losses and head losses. Power losses increase the shaft power required to drive the pump but does not directly affect the head delivered, while head losses directly reduce the head from the ideal value.

2.2.1 Disc Friction Loss

When a rotor spins in a fluid, the shear stress in the fluid acts on the rotor faces as a drag torque. In most centrifugal pumps the impeller is broadly disc shaped, so this is called disc friction loss. Taking the main parameters of the equation from Gulich [5], the power lost to disc friction scales as

$$P_{RR} \approx k_{RR} \rho \omega^3 r_2^5 \quad (9)$$

where k_{RR} is a friction coefficient that falls slowly with Reynolds number. By dividing this by the useful power $P_{hyd} = \rho g Q H$ and substituting the head coefficient $H = \psi u_2^2 / 2g$ with $u_2 = \omega r_2$ gives:

$$\frac{P_{RR}}{P_{hyd}} \approx \frac{k_{RR} \rho \omega^3 r_2^5}{\rho g Q H} \approx \frac{k_{RR} \omega^3 r_2^5}{g Q} \cdot \frac{2g}{\psi \omega^2 r_2^2} = \frac{2k_{RR} \omega r_2^3}{\psi Q} \quad (10)$$

Then, by substituting the head coefficient into specific speed and rearranging for Q :

$$n_q = \frac{n\sqrt{Q}}{H^{3/4}} \propto \frac{\omega\sqrt{Q}}{(\psi\omega^2 r_2^2)^{3/4}} = \frac{\sqrt{Q}}{\psi^{3/4} \omega^{1/2} r_2^{3/2}} \Rightarrow n_q^2 \propto \frac{Q}{\psi^{3/2} \omega r_2^3} \Rightarrow Q \propto n_q^2 \psi^{3/2} \omega r_2^3 \quad (11)$$

Back into the ratio:

$$\frac{P_{RR}}{P_{hyd}} \approx \frac{2k_{RR} \omega r_2^3}{\psi Q} \propto \frac{k_{RR} \omega r_2^3}{\psi \cdot n_q^2 \psi^{3/2} \omega r_2^3} = \boxed{\frac{k_{RR}}{n_q^2 \psi^{5/2}}} \quad (12)$$

This is the reason low specific speed pumps cannot reach high efficiency. The relative disc friction scales as $1/n_q^2$, so halving the specific speed quadruples the share of the input power lost to the disc. As an example point on the size of this, Gülich gives the disc friction as roughly 30% of the useful power of the impeller at $n_q = 10$, $\psi \approx 1$ and $\text{Re} = 10^7$ [5]. Gülich provides fig. 3 to show this relationship visually.

The head coefficient in the denominator of eq. (12) also points the pump designer to design a pump with a higher head coefficient as $P_{RR} \propto \psi^{-5/2}$. For a fixed desired head H and rotational speed n , a high head coefficient means a smaller tip speed and thus a smaller diameter can be derived from ??:

$$u_2 = \sqrt{\frac{2gH}{\psi}} = \frac{\pi d_2 n}{60} \quad (13)$$

Since $P_{RR} \sim r_2^5$ shrinking the diameter collapses the disc friction. This is why Gülich recommends maximising the head coefficient at low specific speed.




Figure 3: Disc friction loss vs specific speed n_q after Gülich. At low specific speed the disc friction dominates.

2.2.2 Hydraulic Losses

fig. 4 shows the hydraulic loss breakdown against specific speed. At low specific speed the impeller blade losses are small, because the velocities of the flow relative to the blades are low, while the volute and the discharge nozzle losses become the next largest term.

2.3 The Barske Partial-Emission Pump

The Barske pump, also known as the partial-emission pump [?], forced vortex pump [16] is a type of centrifugal pump found to be effective in these conditions. The Barske Pump is very simple in geometry as shown in fig. 5b as compared to a conventional pump such as fig. 5a. The impeller consists of a flat disc with straight radial blades. The volute is swapped for cylindrical (annular) casing, with a divergent diffuser placed tangent to the casing. Because the fluid leaves the impeller at high velocity relative to both the casing and the diffuser, the surface finish becomes a primary concern for efficiency at this scale [?]. Gülich also notes that for $n_q < 12$ an annular casing can reach higher efficiencies than a volute, the spiral collector of a conventional pump [?], which has the side benefit of being far simpler to manufacture, a real advantage at small scale where tight tolerances are hard to hold. Conversely, as the losses in the impeller are small, the Barske impeller surface finish is not critical and can be left rough.






Figure 4: Breakdown of pump losses against specific speed, after Gülich. At low specific speed the disc friction dominates while the impeller (blade) losses are small.



(a) Conventional shrouded full emission impeller




(b) Barske open partial emission impeller

Figure 5: Comparison of the conventional and Barske pump architectures. The Barske impeller is open, has straight radial blades, and discharges into an annular casing with a single tangential diffuser.

The Barske impeller pump design which was developed for the need for manufacturing simplicity and low specific speed applications [17] became one of the main centrifugal pump designs at this specific speed. The Barske impeller operates differently to a normal full emission pump. In a conventional centrifugal pump, impeller blade geometry aims to perfectly guide fluid flow along the blade surfaces in a smooth spiral streamline out of the impeller into the volute [5]. The Barske impeller is instead designed to induce almost a pure forced vortex flow where $u = \omega r$ and the fluid is essentially rotating as a solid body with the impeller [17] where meridional or radially outward flow is negligible [18]. This also explains the unimportance of surface finish on the blades, as low relative velocity between the fluid and the impeller means lower friction losses. Another difference between conventional impellers and the barske impeller is the absence of shrouds. The open impeller choice is to further reduce disc friction losses as in the case of radial impellers, shroud friction far exceeds contributions the contribution of all other components [5]. Conventional impellers uses shrouds to guide the flow and reduce secondary flows, but as the Barske impeller operates on a wholly different principle, this shroud is not needed. Removing the shrouds also reduces axial thrust loads on the impeller as there is less surface area for the fluid to push against, which assists with sealing and mechanical design of the pump shaft.

2.3.1 Barske Pump Performance

To predict the performance of a Barske pump, Barske starts by assuming that the flow is nearly a pure forced vortex as shown in fig. 6. He also assumes the relative velocity w is assumed to be negligible. This turns eq. (4) into eq. (14), which is the theoretical static pressure rise of a Barske impeller.



$$\Delta p_{st} = \frac{\rho}{2} (u_2^2 - u_1^2) \quad (14)$$

The kinetic energy increase assuming negligible inlet prerotation is:

$$q = \frac{\rho}{2} u_2^2 \quad (15)$$

eq. (15) is the theoretical dynamic pressure a barske impeller generates at the blade tips. In a barske pump, the diffuser is responsible for converting this kinetic energy into static pressure by slowing down the fluid in an expanding diffuser. Barske introduces a loss coefficient for the kinetic energy which can be recovered through the diffuser to be between 0.2 and 0.5. Barske uses the symbol ψ for this coefficient, but as it conflicts with the commonly used symbol for head coefficient, this paper will instead use k_d . Combining the static and kinetic pressure rise, the total increase in pressure is:

$$\Delta p = \Delta p_{st} + k_d q = \frac{1}{2} \rho ((1 + k_d) u_2^2 - u_1^2) \quad (16)$$

This simple model is used to generate the dimensions in section 2.3.2, but a more refined model from Lock [16] is described in section 2.3.4 to more accurately predict the full characteristics of the pump at any operating point.

2.3.2 Barske Sizing Method

The barske pump is sized by the methods provided by barske [18] with the assistance of Gulich. First the inlet is sized by choosing a reasonable inlet velocity and calculating the inlet area:

$$d_0 = \sqrt{\frac{4\dot{m}}{\pi \rho c_0}} \quad (17)$$

The impeller blade inlet diameter is enlarged by a small amount as some pre-rotation is desirable for increased head. For example, $d_1 \sim 1.1d_0$.

By substituting $u_2 = \pi n d_2 / 60$ into eq. (16) and solving for d_2 , the required impeller tip diameter can be calculated from mass continuity:

$$d_2 = \sqrt{\frac{1}{1 + k_d} \left(\frac{7200 \Delta p}{\rho n^2 \pi^2} + d_1^2 \right)} \quad (18)$$

Barske then gives these guidelines for other dimensions of the pump:

$$s_{ax} \leq \min \left(0.75, \frac{d_2}{100} \right) \quad b_1 \geq \frac{1}{4} d_1 \quad b_2 \geq \max \left(b_1 \frac{d_1}{d_2}, 3s_{ax} \right) \quad (19)$$

For the annular casing sizing, Gulich's guideline where $B/H = 1.5$ to 2.5 can be followed:

$$B = 2s_{ax} + b_2 \quad H = B/2 \quad (20)$$

To size the diffuser, Barske suggests sizing the diffuser throat to be around 0.8 to 0.9 of u_2 , with the area of the diffuser outlet to be 3-4 times the area of the diffuser throat.

2.3.3 Efficiency and Disc Friction

Barske assumes that the disc friction losses can be approximated as a circular disc in a rotating fluid. Converting the equation into metric units gives:

$$P_{RR}[\text{W}] = 1956 \times \rho \nu^{0.2} \left(\frac{n}{1000} \right)^{2.8} (d_2^{4.6} + 4.6 d_1^{3.6} b_1) ?? \quad (21)$$

As the hydraulic efficiency is defined as the useful power out of the pump over the total power into the pump, efficiency can be defined as:

$$\eta_h = \frac{\text{Useful power}}{\text{Input power}} = \frac{P}{P_{th} + P_{RR}} = \frac{Q \Delta p}{Q \Delta p_{th} + P_{RR}} = \frac{\Delta p}{\Delta p_{th} + P_{RR}/Q} \quad (22)$$

If total shaft efficiency is desired, the mechanical losses P_m can be included:

$$\eta = \frac{\Delta p}{\Delta p_{th} + (P_{RR} + P_m)/Q} \quad (23)$$

2.3.4 Lock's Refined Model

Lock provides a refined model which takes into account prerotation, nozzle losses and correction coefficients taking into account theoretical two dimensional flow solutions by A. Busemann and Wislicenus [16, 19]. Lock uses busemann's corrections and derives a refined total head generated by the impeller H_{T2} as eq. (24), where C_H and h_0 are the Buseman correction factors taken from his figure 10A and 10B respectively. K_1 is the prerotation factor which he says himself is arbitrary, and Q_{opt} is the optimum flow rate at which the pump operates at maximum efficiency.

$$H_{T2} = h_0 \frac{u_2^2}{g} - C_H K_1 \left(1 - \frac{Q}{Q_{opt}}\right) \frac{d_1}{d_2} \frac{u_2^2}{g} \quad (24)$$

He then uses a diffuser loss coefficient $\zeta_D = 0.194$ to account for diffuser losses H_{NL} as shown in eq. (25). This coefficient was taken from the Hydraulic Institute's Pipe Friction Manual [20].

$$H_{NL} = \zeta_D \left[1 - \left(\frac{d_3}{d_4}\right)^2\right]^2 \frac{c_3^2}{2g} \quad (25)$$

Finally, to find the static head developed across the pump, the total head generated by the diffuser H_{T2} is reduced by the diffuser losses H_{NL} , dynamic head at the diffuser exit $c_4^2/2g$ and the dynamic head at the impeller inlet $c_0^2/2g$ as shown in eq. (26).

$$H = H_{T2} - H_{NL} - \frac{c_4^2}{2g} + \frac{c_0^2}{2g} \quad (26)$$

Equation eq. (24) requires the parameter Q_{opt} , which is solved by expressing eq. (26) as a function of flow rate Q and taking the derivative with respect to Q and setting it to zero. By expressing $c^2/2g$ by $(8/g\pi^2)Q^2/d^4$ with $c = 4Q/\pi d^2$, the head can be expressed as a function of flow rate Q as shown in eq. (27).

$$H = h_0 \frac{u_2^2}{g} - C_H K_1 \left(1 - \frac{Q}{Q_{opt}}\right) \frac{d_1}{d_2} \frac{u_2^2}{g} - \frac{8Q^2}{g\pi^2} \left(\frac{\zeta_D}{d_3^4} + \frac{1}{d_4^4} - \frac{1}{d_0^4}\right) \quad (27)$$

Solving the derivative for Q_{opt} gives the optimum flow rate as shown in eq. (28).

$$Q_{opt} = \sqrt{\frac{h_0 u_2^2}{\frac{24}{\pi^2} \left(\frac{\zeta_D}{d_3^4} \left(1 - \left(\frac{d_3}{d_4}\right)^2\right) + \frac{1}{d_4^4} - \frac{1}{d_0^4}\right)}} \quad (28)$$

Lock and Barske suggest that the flow cutoff point is limited by cavitation at the diffuser throat. To find the static pressure at the diffuser throat, reversing the transfer between dynamic head into static head provided by the previous equations:

$$H_3 = H + \frac{8Q^2}{g\pi^2} \left(\frac{\zeta_D}{d_3^4} \left(1 - \left(\frac{d_3}{d_4}\right)^2\right) + \frac{1}{d_4^4} - \frac{1}{d_3^4}\right) \quad (29)$$

Then solving for the Q at which H_3 is equal to vapor pressure head $H_{vap} = \frac{1}{\rho g} (p_{vap} - p_{inlet})$ gives the flow cutoff point.

An observation by Lock should be kept in mind when his model is compared to data later. He notes that rounding of the peripheral leading edges reduces the effective head [16]. This is evidently not captured in the model and could one of the many reasons for discrepancies between theory and experiment.

2.4 Turbine Theory

2.4.1 Impulse Turbines

Turbines work with the same Euler turbine equation. In the supersonic impulse turbine design, the blades are only occupy a small outer portion of the blisk ($d_3 \approx d_4 \approx d_{mean}$, $u_3 \approx u_4 \approx u$), so the euler turbine equation eq. (2) can be simplified:

$$\Delta h_{use} = c_{3u} u_3 - c_{4u} u_4 = u(c_{3u} - c_{4u}) \quad (30)$$

This following derivation follows from Sudhof's [12]. From eq. (30), it is understood that a higher flow velocity difference $c_{3u} - c_{4u}$ per unit mass will lead to a higher specific work Δh_{use} according to equation eq. (3). Maximizing $c_{3u} - c_{4u}$ as visualized by fig. 7 is done by maximizing the absolute velocity and as close to 180° of turning as possible. For this reason, gas generator cycle turbines tend to take advantage of the high pressure ratios and thus supersonic velocities. The amount of flow turning is usually limited by geometrical and mechanical design reasons.

2.4.2 Impulse Turbine Efficiency

The ideal efficiency of the impulse stage follows from eq. (30) and the velocity triangles in fig. 7. At the rotor inlet and exit the circumferential components of the absolute and relative velocities are related by

$$c_{3u} = w_{3u} + u, \quad -w_{4u} = -c_{4u} + u \Rightarrow c_{4u} = u + w_{4u} \quad (31)$$

The ideal impulse blade turns the relative flow without slowing it down, so the exit relative velocity mirrors the inlet one, $w_{4u} = -w_{3u}$. Substituting into eq. (30),

$$\Delta h_{use} = u(c_{3u} - c_{4u}) = u[(w_{3u} + u) - (u + w_{4u})] = 2u w_{3u} = 2u(c_{3u} - u) \quad (32)$$

As ideally, nozzle exit circumferential velocity equals the circumferential velocity at the blade inlet, $c_{2u} = c_{3u}$, eq. (32) gives the required circumferential velocity the nozzle must deliver for a given specific work Δh_{use} and blade speed u . The nozzle exit absolute velocity c_3 is related to the circumferential component by the nozzle angle β_3 measured from the circumferential direction as shown in eq. (33).

$$c_{3u} = \frac{\Delta h_{use}}{2u} + u, \quad c_3 = \frac{c_{3u}}{\cos \beta_3}, \quad c_{3m} = c_3 \sin \beta_3 \quad (33)$$

Dividing the work eq. (32) by the kinetic energy $c_3^2/2$ the nozzle supplies gives the stage efficiency. In a pure impulse stage the entire expansion happens in the nozzle, so the available energy per unit mass is the jet kinetic energy $c_3^2/2$, and with $c_{3u} = c_3 \cos \beta_3$.

$$\eta_{ideal} = \frac{2u(c_3 \cos \beta_3 - u)}{c_3^2/2} = 4 \frac{u}{c_3} \left(\cos \beta_3 - \frac{u}{c_3} \right) \quad (34)$$

The efficiency depends only on the blade to jet speed ratio u/c_3 and the nozzle angle. By taking the derivative of eq. (34) and setting it to zero, the optimum sits at $u/c_3 = \cos \beta_3/2$. For most turbines with a low β_3 the optimum is around $u/c_3 \approx 0.5$.

The jet spouting velocity c_3 used in this ratio is the spouting velocity, the velocity reached by an ideal isentropic expansion of the ideal gas over the full stage pressure ratio,

$$c_3 = \sqrt{2 \Delta h_{1 \rightarrow 3}} = \sqrt{2 c_p T_{01} \left[1 - \left(\frac{p_3}{p_{01}} \right)^{\frac{\gamma-1}{\gamma}} \right]} \quad (35)$$

For 300 K air with a pressure ratio of 10, $c_3 = 538$ m/s. A 100 mm diameter turbine on a 20,000 RPM shaft has a blade speed of around 105 m/s, leading to a u/c_3 of 0.19. The spouting velocity of even a moderate pressure ratio gas generator at a higher outlet temperature can quickly reach up to velocities c_3 from 800 m/s upwards, so u/c_3 is forced far below the optimum of around 0.5. This is a fundamental limitation of small diameter turbines.

2.4.3 Impulse vs Reaction Turbines

NASA published fig. 8a in its SP-8110 showing that for low u/c_3 turbines, impulse turbines are more efficient, even if reaction turbines can have a higher overall efficiency. In addition, the same conclusion is drawn by comparing the influence of tip clearance on the two types, where impulse turbines are more robust to tip clearance as shown by fig. 8b. This is especially important for small scale turbines where manufacturing tolerances are more difficult to achieve and contribute to more significant losses [?].




Figure 7: Impulse turbine velocity triangle nomenclature at the rotor inlet (station 3) and exit (station 4).




Figure 8: Comparison of efficiency between impulse and reaction turbines against u/c_3 and tip clearance.

2.4.4 Blade Height and Partial Admission

Another problem with designing small turbines is with the low blade height required. By calculating the mass flux through the turbine, the blade height can be designed:

$$H = \frac{\dot{m}}{\rho_3 c_{3m} d_{\text{mean}}} \quad (36)$$

Where ρ_3 is the density of the turbine gas at the turbine inlet calculated using isentropic gas relations. Using the example turbine above (a 2 kW stage with $\dot{m} = 23.0 \text{ g/s}$ at $\rho_3 = 2.24 \text{ kg/m}^3$), the required full admission blade height would be 0.74 mm, which is far too small to manufacture or to run without the wall boundary layers swallowing the whole passage. Blade height as small as 1.25 mm on a turbine diameter of 50 mm has been reported to work in practice by [21]. This is in line with their internal design rules, where a blade height to mean diameter of h/d_{mean} from 0.025 to 0.10 is recommended. However, NASA's SP-8107 recommends a minimum height of 3.8 mm [22]. By introducing partial admission, the mass flow through the turbine can be restricted to a smaller arc around the annulus at a slight cost to efficiency. The partial admission ratio ζ can be included into the blade height formula as so:

$$H = \frac{\dot{m}}{\zeta \rho_3 c_{3m} d_{\text{mean}}} \quad (37)$$

By reducing the admission to $\zeta = 15\%$, the same mass flow is forced through a smaller arc of the annulus and the blade height is increased to 4.92 mm. The blade height matters because it sets the blade aspect ratio H/c , the blade height over chord, which fixes how much of the passage the endwall boundary layers block.

Ohlsson found that blade efficiency and nozzle efficiency both drop with low aspect ratio blades. He tested 4 turbines with aspect ratios ranging from 0.07 and 0.7 on a 4 inch diameter turbine. He found that the efficiency of both the nozzle and the rotor dropped linearly to the inverse of the aspect ratio, as shown in eq. (38) [23].

$$\eta_{\text{nozzle}} = 0.92 - 0.016(c_{\text{nozzle}}/H_{\text{nozzle}}) \quad \eta_{\text{rotor}} = 0.91 - 0.10(c_{\text{rotor}}/H_{\text{rotor}}) \quad (38)$$

This loss of efficiency with low aspect ratio has to be balanced with the loss of efficiency with partial admission. Weiss provides eq. (41) for the power loss having to drag the non-admitted arc through stagnant air as a function of partial admission ratio ζ and blade height H . The other loss present only in partial admission turbines is the loss associated with the filling and emptying the blade channels. Ohlsson found that having a single continuous arc of admission was more efficient than distributing arcs of admission around the annulus as the entering loss is repeated [24]. NASA SP-8110 agrees with this, but also notes that sometimes this continuous nozzle arc has to be violated if designs cannot sustain the uneven loads [25].

2.4.5 Loss Model

The main loss model used in the design of the turbine is the one provided by Weiß [?]. There are more general loss models provided by texts such as NASA SP-290 [26], giving loss models for tip-clearance, disk friction, partial admission and incidence losses. However, those models were built on large full-admission, subsonic to transonic turbines. Weiss specifically derived his loss model for the specialized application of a supersonic impulse turbines at small scales (1-200kW) [21]. As the regime of the turbine considered in this thesis matches closer to Weiss's model compared to SP-290's model, Weiss's model is used. Weiss describes different models lead to stage efficiency differences of about

10% points. Derived from rocket turbopumps literature and adjusted by in-house measurements, Weiss provides three empirical relations to form his loss model. Weiss references Traupel [27], Craig [28] and Kacker's [4] models for these larger subsonic full admission turbines.

$$k_N = \sqrt{1 - (0.0029 M_3^3 - 0.0502 M_3^2 + 0.2241 M_3 - 0.0877)} \quad (39)$$

eq. (39) is the nozzle loss coefficient, relating the actual velocity to the theoretical isentropic velocity by $k_N = c_{No}/c_{No, is}$.

$$\begin{aligned} k_R = & 0.957 - 3.62 \times 10^{-4} \Delta\beta - 2.58 \times 10^{-2} M_{w3} \\ & + 6.39 \times 10^{-6} \Delta\beta^2 + 6.74 \times 10^{-2} M_{w3}^2 \\ & - 7.53 \times 10^{-8} \Delta\beta^3 - 4.30 \times 10^{-2} M_{w3}^3 \\ & - 2.38 \times 10^{-4} \Delta\beta M_{w3} + 1.45 \times 10^{-6} \Delta\beta^2 M_{w3} + 4.25 \times 10^{-5} \Delta\beta M_{w3}^2 \end{aligned} \quad (40)$$

eq. (40) is the loss of velocity along the blade passage through a theoretically impulse blade, relating the actual velocity to the theoretical velocity by $k_R = w_{exit}/w_{inlet}$.

$$P_v = \frac{1.85}{2} (1 - \zeta) \rho_3 \left(\frac{n}{60}\right)^3 d_m^4 (4.5 H) \quad (41)$$

Finally, eq. (41) captures the losses due to partial admission. Weiss calls this loss ventilation losses, but it can also be called windage losses. Ventilation losses refers to the non-admitted arc being dragged through stagnant air.

2.5 Turbine Blade Design

The design so far is based on 1D mean line theory. The design of the actual blade profile is what will guide the supersonic flow from the inlet direction to the outlet direction to maximize $c_{3u} - c_{4u}$. The basis of supersonic impulse blade profiling is often accomplished using an application of the Method of Characteristics (MOC) to transition a uniform flow field into vortex flow.

2.5.1 Method of Characteristics for Supersonic Impulse Blade Design

Vortex flow is a special type of supersonic flow in which every streamline follows a concentric path around a central point. This flow field was first discovered by A. Busemann [29], achieved by conditions where expansion and compression waves cancel each other to allow shockless rotation of the flow field. The vortex flow is bounded by the two circular arcs of the surfaces of which a desired surface Mach number is achieved. Boxer then first developed the method to transition uniform flow into vortex flow with MOC [10]. This method generates the profile for an inlet Mach number, turning angle and the mach numbers on the blade surfaces. Later analysis will need to be required to choose these desired Mach numbers.

Turbine blade terminology is based on the blade's upper and lower surfaces as shown in Figure 9. The top surface is the convex one, and the bottom surface as the concave one. This is in relation to the solid blades themselves as opposed to an alternate designation by the top and bottom of the blade passage. Supersonic vortex flow satisfies the equation:

$$cr = \text{constant} \quad (42)$$

Boxer [10] and Goldman [11] nondimensionalizes eq. (42) using the critical velocity $M^* = c/a^*$ where $a^* = \sqrt{\gamma RT^*}$ is the speed of sound at the sonic point. As a^* only depends on stagnation temperature, it is constant along any streamline of fixed stagnation enthalpy. Then, a nondimensional radius r^* is introduced as the sonic velocity streamline in the vortex field, giving the following condition:




Figure 1. - Typical supersonic blade section. (All coordinates are made dimensionless by dividing by r^* .)

Figure 9: Typical MOC blade terminology.

$$M^* r^* = 1 \quad (43)$$

Goldman gives an equation [11] to find the Prandtl-Meyer angle from the critical mach number M^* as:

$$\nu(M) = \frac{\pi}{4} \left(\sqrt{\frac{\gamma+1}{\gamma-1}} - 1 \right) + \frac{1}{2} \left(\sqrt{\frac{\gamma+1}{\gamma-1}} \arcsin [(\gamma-1)M^{*2} - \gamma] + \arcsin \left(\frac{\gamma+1}{M^{*2}} - \gamma \right) \right) \quad (44)$$

And the converting between Mach number and Critical Mach number is given by:

$$M^* = \sqrt{\frac{(\gamma+1)M^2/2}{1 + (\gamma-1)M^2/2}} \quad (45)$$

The rest of the methodology to design the blade profile can be found in Goldman's paper [11] and will not be repeated here. Equations eq. (43) and eq. (45) are highlighted as they can be used to derive the nondimensional radius of the upper and lower surfaces of the blade, which will be important in the following discussion on surface Mach number selection. It is important to note that the inlet mach number for starting here is computed not with the absolute velocity c_3 but with the relative velocity w_3 , as the flow will be turning inside the rotating frame of the turbine blade. This distinction is made as the relative velocity is dependent on the rotational speed of the turbine, meaning that this blade profiling is optimized for only the design point of the turbine. The surface Mach numbers are constrained by two mechanisms. Flow separation and supersonic starting.

2.5.2 Flow Separation

Separation occurs in high adverse pressure gradients. In supersonic flow, this happens whenever the flow is decelerating along the surface. There are two main regions on the blade surfaces which separation can occur. At the upper surface, the inlet transition arc accelerates the flow from the inlet velocity until the vortex flow, then decelerates the flow until the outlet. At the lower surface, the inlet transition arc decelerates the flow from the inlet velocity until the vortex flow, then accelerates the flow until the outlet. Goldman believes that separation on the lower surface is probably not as important as the flow would tend to reattach shortly as the pressure gradient becomes favourable again [2]. Goldman uses the value of the incompressible form factor H_i along the blade surface to predict separation, where Schlichting [30] found that separation usually occurs in the range of H_i from 1.8 to 2.4. The variation of H_i along the blade surface can be seen in fig. 10a.






Figure 10: Goldman's published figures describing the distribution of Mach number and incompressible form factor H_i along the blade surfaces. [2]

Sasman and Cresci [31] provides a method to compute the development of the compressible turbulent boundary layer and thus find the incompressible form factor H_i along both surfaces. In this method, the edge Mach number distribution was taken from the MOC blade solution and fed into the their compressible integral method. The boundary layer was started as a turbulent flat plate with $\theta_0/c = 0.036 \text{Re}_{s_0}^{-1/5}$, using the prandtl $u/U = (y/\delta)^{1/7}$ and $\delta/c = 0.37 \text{Re}_{s_0}^{-1/5}$ [32]. The Reynolds number Re_{s_0} is calculated with the blade inlet density ρ_3 , relative velocity w_3 and the chord length c . The shape factor $H_{i,0}$ is chosen to the value which the integration relaxes to within the first few percent of chord regardless of the start value. Once this calculation is done, the incompressible form factor H_i can then be used to evaluate if generated blade profile, and thus the chosen surface Mach numbers will lead to separation and where and feed into the design loop. This methodology was implemented in Python and validated against Goldman's published figures, as shown in fig. 11.



(a) Attempted reproduction of Goldman's incompressible form factor H_i along the blade surfaces



(b) Attempted reproduction of Goldman's distribution of Mach number along the blade surfaces

Figure 11: Validation of Sasman and Cresci's method to compute the development of the compressible turbulent boundary layer against Goldman's published figures.

fig. 11 a similar H_i and M distribution along the blade surfaces as Goldman's published figures with a few dissimilarities. The first difference is that the fraction of chord the transition arcs taken up in the code is slightly larger than Goldman's published figures. The different edge mach number distribution leads to a different H_i distribution because the boundary layer growth is dependent on the edge mach number distribution. This means that there could be differences in initial conditions or ODE solving approach. However, the general trend and magnitudes of H_i where the lower surface has a spike in H_i in its deceleration transition arc and the upper surface has a spike in H_i in its deceleration transition arc allows the code to be used with caution even if not fully validated.

It is important to note that Goldman provides another set of equations in his NASA TN D-4421 1968 paper [11] that has been shown to not be conservative enough, with tests by Erikson on the development of the HM60 engine saying that his criteria is a little too optimistic [33]. The Sasman method described here is from Goldman's NASA TM X-2095 paper [2].

2.5.3 Supersonic Starting

On startup before the turbine passage runs supersonically, a detached bow shock stands ahead of the leading edges. The flow behind this normal shock is subsonic and has lost a significant amount of total pressure. For the turbine to operate nominally with supersonic flow, the passage must be able to "swallow" this shock, allowing the shock to move through the whole passage.

To do so, the post shock flow with a reduced total pressure must have enough of a flow area pass the required mass flow similar to the choked flow condition. A similar condition is the unstart of a supersonic wind tunnel or a supersonic internal intake. However, Boxer notes that due to the large velocity gradient between the channel walls due to the turning, the flow cannot be assumed one directional as are the case in the provided examples. Goldman provides the condition [11] accounting for the "reduction of mass flow due to curvilinear flow" to calculate the maximum inlet design mach number to ensure starting as:

$$\frac{p_{02}}{p_{01}}(M_i) \geq \frac{Q}{1 - C} \quad (46)$$

Where p_{02}/p_{01} is the total pressure loss across the normal shock, which is a function of M_i , the inlet design mach number. The right side of equation (46) involves nondimensional parameters Q and C which can be solved for through equation 27, 34a and 34b as a function of the surface mach numbers M_l^* and M_u^* . Q is named the vortex parameter [12] and C is the reduction in mass flow due to two-dimensional flow. Solving this equation for M_i gives the maximum inlet design mach number to ensure starting. Once again, this maximum inlet mach number is not based on absolute velocity c_3 but on the relative velocity w_3 . The relative inlet mach number at the design point is lower than at startup, as $w_{3u} = c_{3u} - u$ following the velocity triangle shown in fig. 7. The starting condition at eq. (46) should be more conservatively evaluated at standstill to ensure that the turbine will start at all rotational speeds.

Historically, starting was a major problem for supersonic turbines. Before the theory was established, Colclough had to build a special jig in which every blade could be pivoted to vary the contraction until the blade started [29].

2.5.4 Surface Mach Number Selection

The separation criterion described in section 2.5.2 limits the acceleration of the flow along the upper surface, and the deceleration of the flow along the lower surface. Then, the starting criterion described in section 2.5.3 provides an

make s
this ex
plains
stands

additional limit on the inlet design mach number based on these surface mach numbers.

However, Goldman notes that for optimum efficiency, the maximum spread of surface number leads to maximum efficiencies [2]. It comes from the fact that a loss of velocity across the impulse blade leads to a loss of kinetic energy transfer to the blades, so he posits the efficiency of an impulse blade to be:

$$\eta = \left(\frac{w_{exit}}{w_{exit,ideal}} \right)^2 \quad (47)$$

eq. (47) is nearly the same as Weiss' eq. (40) loss. Weiss derived his empirical model only of 1D parameters such as inlet mach number and the angled the flow is turned. What this efficiency tries to capture is the boundary layer friction losses, shocks, and exit wake mixing losses. The effect of spreading the surface mach numbers becomes clear by looking at the vortex equation eq. (43). The larger the mach number spread, the larger the difference in R^* between the upper and lower surface, the larger physical passage width as shown in fig. 12. The wider the channel compared to the blade chord, the lower fraction of the boundary layer thickness to passage width, the lower the wetted surface area per unit flow, and thus the lower the losses. This is the challenge of supersonic turbine blade design, maximum efficiency is achieved by riding along the edge of separation and starting.




Figure 12: The effect of surface Mach number spread on the blade passage, for the same inlet conditions. A narrow spread produces thin passage where the boundary layers occupy a large fraction of the width, while a wide spread opens the passage up.

2.5.5 Finite Leading Edge

In section 2.5.1, the upper and lower surface are mathematically designed to produce no shocks in transitioning the uniform flow from the nozzle exit into the vortex flow. For no shocks to form, both surfaces must be perfectly parallel to the starting flow. This is problematic because this implies the point where the two surfaces intersect at the leading edge, the angle between the upper and lower surfaces is zero. This creates an impossible to manufacture zero thickness leading edge. Boxer suggests a few methods to solve this issue. He separates design into turbines with a subsonic or supersonic axial velocity component.

Boxer [10] describes a few finite leading edge treatments depending on the axial velocity component. For subsonic axial velocity turbines, either lower or upper surface can be designed with an incidence angle to the inlet flow. Angling the upper convex surface and keeping the lower concave surface parallel to the inlet flow, the compressive oblique shock will be generated along the region between the inlet and the nozzle exit, affecting the flow in the next blade passage. Kantrowitz shows that in steady state a compression shock of equal strength will be created to obtain the steady state condition [34]. To solve this, the lower concave surface can be angled so that the shock stays within the blade passage and does not affect the upstream flow as shown in fig. 13. The oblique compression shock can then be designed to intersect the upper surface at an angle to fully cancel out the shock. For supersonic axial velocity turbines, a wedge can be designed on the convex surface with a low enough angle from the design inlet flow so that the shock stays within the blade passage and can be cancelled out by a kink on the concave surface.




Figure 13: Finite leading edge treatments for supersonic blades: incidence angling of one surface, in passage shock cancellation, and the small wedge used to cancel the resulting compression shock.

2.5.6 Nozzle Design

The nozzle is sized with the isentropic choked mass flow equation eq. (48).

$$\dot{m} = \frac{A_{th} p_{01}}{\sqrt{T_{01}}} \sqrt{\frac{\gamma}{R}} \left(\frac{2}{\gamma + 1} \right)^{\frac{\gamma+1}{2(\gamma-1)}} \quad (48)$$

While the throat sets the mass flow, the ratio of the exit area to the throat area sets the exit Mach number, through the isentropic area relation eq. (49).

$$\frac{A_3}{A_{th}} = \frac{1}{M_3} \left[\frac{2}{\gamma + 1} \left(1 + \frac{\gamma - 1}{2} M_3^2 \right) \right]^{\frac{\gamma+1}{2(\gamma-1)}} \quad (49)$$

Historically, the optimal nozzle design for an ideal inviscid gas was designed with the Method of Characteristics as well. Rao provides a method to achieve this [35]. NASA special publication 8120 explains that a single canted parabola closely approximates the ideal nozzle contour and should be used for high performance nozzles [3]. In this thesis, the nozzle was designed as a simple conical nozzle with a 7° degree half angle. It can be seen from fig. 14 that the performance of a conical nozzle for low area ratios lead to a efficiency loss below 2%.




Figure 7. — Variation of theoretical nozzle divergence efficiency with area ratio and divergence half-angle.

3 Design

The turbopump design point for this thesis was chosen from the capabilities of the test rig. The design parameters for the pump and turbine is shown in table 1 and this section explains how each number was chosen. The RPM limit was set by the maximum speed of the Magtrol TM306 inline torque meter and the AHB-3 hysteresis brake at 20,000 RPM. The pressure rise and flow rate was chosen to study the low specific regime. The supply pump was decided to be Hozelock's JET 3000 K7 Jet pump as it was available in the department and had a published performance curve. At 0.3 kg/s, the supply pump had a head of around 2.2 m. Then, the pressure rise of the pump was chosen to be 20 bar for a specific speed of 6.4.


Table 1: Turbopump system design point.

Symbol	Parameter	Value
n	design shaft speed	20 000 rpm
Q	pump design volume flow rate	0.3 L/s
Δp	pump design pressure rise	20 bar
n_q	pump specific speed (rpm, m ³ /s, m)	6.4
P	turbine design shaft power	2.6 kW
p_{01}	turbine design inlet total pressure	7.65 bar
–	pump working fluid	water
–	turbine working fluid	compressed air

3.1 Pump Design

3.1.1 Sizing

Following the global design point parameters, the pump was sized using the Barske as described in section 2.3.2 to give the dimensions shown in table 2 and labelled by fig. 15.

**Figure 15:** The sized pump geometry drawn to scale. The meridional section (left) and plan view (right).

The design starts following section 2.3.2 from what Barske considers a reasonable inlet velocity. 1.0 m/s was chosen. Higher inlet velocities lead to higher NPSHR. This fixes the eye diameter d_0 . The eye is then enlarged to the blade leading edge diameter d_1 to allow the deliberate prerotation Barske recommends. The inlet and exit blade heights follow from continuity following eq. (19). The impeller tip diameter d_2 comes from the recovery equation eq. (18) with a deliberately conservative diffuser recovery coefficient of $k_d = 0.2$. A conservative k_d oversizes the impeller to make sure the desired head is achieved and can be adjusted in future iterations. The sized values are listed in table 2.

This geometry is then put into Lock's model to predict the head curve fig. 34 and NPSHR fig. 39 to be compared with experimental data in section 5.

Table 2: Pump design summary. The impeller dimensions are the sizing code output; the diffuser throat d_3 and exit d_4 are the as-built values, which depart from the sized values for the reasons given in the text.

Symbol	Parameter	Value
d_1	impeller inlet (blade leading-edge) diameter	21.5 mm
d_2	impeller tip diameter	58.5 mm
b_1	blade height at impeller inlet	6.4 mm
b_2	blade height at impeller exit	3.6 mm
z	blade count	6
d_3	diffuser throat diameter (as built)	3.0 mm
d_4	diffuser exit diameter (as built)	9.0 mm
ψ	design head coefficient	1.065
n_q	specific speed (rpm, m ³ /s, m)	6.4

3.1.2 Diffuser

The diffuser is a single conical passage placed tangentially on the annular casing, following Barske's guidance from section 2.3.2. The throat was sized for a throat velocity of 0.8 to 0.9 of u_2 , giving $d_3 = 2.79$ mm, and the exit area was set at 3 to 4 times the throat area, giving $d_4 = 5.58$ mm. Two changes were made to these before the part was made. The throat was opened up to 3.0 mm, rounding the sized value up. The oversize itself is for manufacturing, so the small passage prints and cleans out reliably, but rounding up rather than down was deliberate. The throat is the most cavitation critical dimension in the pump, and a larger throat runs a lower throat velocity, which raises the cavitation limited maximum flow that the results in section 5 show this throat actually sets. The low specific speed optimisation literature points the same way, treating the diffuser throat as a lever to open rather than to minimise [8]. The diffuser exit was then enlarged to 9.0 mm for packaging. The cone sits tangentially on the annular casing, and had to clear the casing wall for the inlet fitting. That over-expands the passage well past Barske's 3 to 4 area ratio guidance, but the extra area is all downstream of the throat on the discharge side, so it costs nothing here. The comparison of this throat sizing against the literature is discussed in section 5.

Barske comments that the number of impeller blades does not seem to be critical, with 3-6 being operated successfully. However, altering the number of blades can be used to eliminate fluid vibrations [18]. Lock provides corrections for blades from 1 to 16 [16].

3.1.3 Mechanical Design




Figure 16: Labeled CAD isotropic and section view of the pump assembly

After the theoretical Barske pump geometry has been sized to deliver the design head at a desired flow rate, it has to then be translated into a manufacturable assembly that satisfies additional practical requirements. The mechanical design has to survive loading conditions such as high rotational speeds and pressures. Then, it also has to be leak

tight, manufacturable and assemblable. A CAD model of the pump assembly that satisfies these requirements is shown in fig. 16.

Material Selection The low pressure rise of 20 bar as a small scale prototype to study rocket engine pumps allowed for a wider and more accommodating material selection criteria. Plastic was chosen for its ability for rapid prototyping and low cost. SLA was chosen instead of FDM for most parts because FDM printing layer by layer creates a porous surface that will not be leak proof at 20 bar. The pump impeller and were printed in Formlabs Tough 2000 resin for this reason. For this thesis, it was realized that although mechanically weaker than Tough 2000, the Formlabs clear resin was found to be a possible material. The pump casing and inlet were printed in clear resin and polished. This allowed for cavitation visualisation in section 5, which turned out to be one of the most valuable measurements of the project. For the bracket that mounted the pump to the test rig, leakage was not a concern so it was printed in PLA for its rigidity and low cost. The pump shaft had to be made of a stronger material for rotordynamic stability at high rotational speeds and high torque, so it was made of stainless steel and machined on the manual lathe and mill in the Imperial Advanced Hackspace.

Sealing Most rotary seals did not work for this application. A lip seal wears out fast at this surface speed and holds very little pressure, a labyrinth seal could not be reliably used with plastic parts due to printing tolerances, and packing has too high friction. This led to the choice of using a mechanical seal. Mechanical seals consist of a spring loaded rotating face running against a stationary face with the only leak path a thin liquid film between two lapped surfaces. The liquid film greatly reduces the friction between the two faces. A John Crane 59U-14 mechanical seal was used. Mechanical seals operate by pressing a rotating face against a stationary face with a thin liquid film in between [36]. For the static seals, two O-rings sized with the [37] were used to seal the inlet against the casing and the casing to the bearing housing. The seal between the inlet and the casing was a piston seal, while the seal between the casing and the bearing housing was a face seal.

Mechanical Losses The mechanical losses of this pump assembly come from the bearings and the mechanical seal. The bearings were 61900 series stainless steel ball bearings chosen for their water resistance and cost. In this design, one bearing is submerged in water, increasing the drag loss. The power loss of the bearing was estimated by SKF's frictional moment model [38]. Karassik gives a formula for mechanical seal friction [36] with eq. (50).

$$\tau_{seal} = p_f A_f r_m f, \quad P_{seal} = \tau_{seal} \omega \quad (50)$$

where B_r is the seal balance ratio built from the mechanical seal face outer and inner diameters d_o , d_i and the balance diameter d_b as shown in fig. 17, $k \approx 0.5$ is the pressure profile factor for the fluid film between the faces assuming a linear pressure distribution, and p_{sp} is the spring force over the face area and Δp is the pressure differential across the seal face [5].

$$p_f = \Delta p (B_r - k) + p_{sp}, \quad B_r = \frac{d_o^2 - d_b^2}{d_o^2 - d_i^2} \quad (51)$$




Figure 17: Geometric dimensions of an OD pressurized the mechanical seal by Karassik [4].

In conventional shrouded impellers, the back face of the impeller is exposed to the the full pressure rise of the pump, contributing to a higher pressure Δp that needs to be sealed across the shaft, leading to higher mechanical seal friction. The Barske impeller is open and the back face is exposed to the suction pressure, which reduces the pressure differential across the seal and therefore the friction.

Concentricity Concentricity is of great importance in high speed rotating machinery. The design takes advantages of shoulders and press fits to ensure the concentricity between every interfacing part as shown in fig. 16.

3.2 Turbine Design

3.2.1 Architecture Selection

Instead of the conventional axial turbine, a radial inflow cantilever, also called a centripetal impulse turbine was chosen. In this design, the flow enters the rotor radially inward through blades cantilevered off the rim of the disc, instead of passing axially through a bladed wheel. The reason for choosing this architecture in this thesis because it is simpler to manufacture. The turbine blisk can be made with 2.5 axis CNC milling, or in this thesis, additively manufactured without angled overhangs. This trade in manufacturing simplicity is balanced by a slight drop in efficiency as Smirnov [39] found in his CFD studies compared to axial or radial inflow reaction stages [40]. However, the radial inflow cantilever is still a layout proven for small supersonic turboexpanders in this exact power and regime [21]. The meanline loss model is the same for the axial and the radial inflow cantilever stage [21], so this is a packaging choice and not a change to the aerodynamic design method. The established rocket turbopump turbine is an axial

flow stage, to the point that the standard NASA design monograph for rocket turbopump turbines treats only axial machines [25], so the choice here of a radial inflow cantilever stage needs justifying.

3.2.2 Design Point and sizing

Turbine sizing has to satisfy many requirements simultaneously to reach the global requirements of a rotational speed of 20 000 rpm at a power of 2.6 kW. Parameters such as diameter d_m , mass flow through the turbine $\dot{m}$, blade inlet angle β_3 , nozzle pressure ratio p_{01}/p_3 have to be balanced against each other to reach a feasible design point. As explained in section 2.4.1, minimizing inlet angle β_3 maximizes flow turning and thus specific work. Preliminary CAD of the radial turbine was used to find that a blade inlet angle of β_3 was the minimum that could be achievable geometrically. The pressure ratio p_{01}/p_3 was chosen so that the design operating point p_3 was above the ambient pressure at 1.1 bar.

After setting these constraints at the design rotational speed and desired turbine generated power, contour plots fig. 18 were generated over the $(d_m, \dot{m})$ plane to study the design space for a possible design point. The nozzle exit mach number and blade height are calculated using eq. (33), eq. (37) as described in section 2.4.1, with empirical predicted efficiency using Weiss's loss model described in section 2.4.5. Blade height was quickly found to be a limiting constraint as shown in fig. 18 and following NASA's SP-8107 for a minimum height above 3.8mm, the requirement was set to 4mm for manufacturability. Many iterations of these contours were studied with varying degrees of admission ζ until a feasible design point was found that balanced a minimal mass flow $\dot{m}$ and mean diameter d_m that satisfies all these constraints. Low mass flow is desirable in a rocket turbopump as every bit of mass flow that flows into the gas generator is loss thrust and thus efficiency to the main engine. A lower turbine diameter leads to lower centrifugal stress and thus lower structural mass and also the goal of this thesis which is to study the design of small turbopumps.




Figure 18: The turbine design space over mean diameter and mass flow, evaluated with the full sizing and loss model at the design speed. The panels show nozzle exit Mach number, blade height and predicted total to static efficiency. Overlaid lines are the design constraints (blade height ≥ 4 mm, nozzle throat ≥ 0.5 mm, $M_3 \leq 1.8$), the shaded region is infeasible, and the marker is the selected design point.

Following this design procedure, a table of the design point parameters is shown in table 3.

Table 3: Turbine design summary

Symbol	Parameter	Value
P	design shaft power	2.6 kW
p_{01}	design inlet total pressure	7.65 bar
T_{01}	design inlet total temperature	300 K
$\dot{m}$	design air mass flow rate	0.0428 kg/s
d_m	mean (pitch) diameter	95 mm
b	rotor blade height	4.0 mm
ζ	degree of admission	0.15
β_3	rotor blade angle (from tangential)	15°
z_N	number of nozzles	3
A_{th}	total nozzle throat area	35.5 mm ²
c_3	design nozzle-exit velocity	464 m/s
M_3	design nozzle-exit Mach number	1.67
M_{w3}	design rotor-inlet relative Mach number	1.33
η_{ts}	design total-to-static efficiency	0.47

3.2.3 Blade Passage Design

The blade passage was generated with the MoC procedure of section 2.5.1 for an inlet relative Mach number of 1.3, with surface Mach numbers $M_l = 1.05$ and $M_u = 1.5$. H_i check touching 2.1 at the exit transition arc on the upper surface, deliberately separation imminent at the design point. The starting margin was left deliberately thin to maximise loading. The Goldman limit for this passage was calculated to be $M_{w3} = 1.408$ against a design value of 1.33. Unfortunately, the starting limit wasn't checked against the Nozzle mach number at a standstill which was 1.67. As a result, the turbine did not have enough torque to bring the relative inlet mach number M_{w3} below the limit. This was a design error that led to the unstart of the rotor during experimental testing, and is discussed in section 5.




Figure 19: The ideal MoC countour and incompressible form factor H_i check for the design surface mach numbers $M_l = 1.05$ and $M_u = 1.5$.

3.2.4 Losses and Predicted Efficiency

Applying the Weiss loss model of section 2.4.5 at the design point gives a nozzle velocity coefficient of $k_N = 0.917$, a rotor velocity coefficient of $k_R = 0.807$, and a ventilation power of 85 W. Together these take the ideal stage efficiency of around 65% down to a predicted total to static efficiency of 0.47.

3.2.5 Blade Geometry Details

Bringing the MoC geometry designed for axial flow into radial flow in CAD led to a few geometric compromises. First of all, the upper and lower surfaces had to be angled by the pitch angle to keep the MoC passage geometry conserved. Due to this, the recommendations by Boxer described in section 2.5.5 could not be followed geometrically. The final profile that was designed in CAD and tested is shown in fig. 20. As can be seen, the rotation of the blade surfaces led to thin inlet as compared to the outlet. The minimum thickness was 0.35 mm to keep the blade manufacturable by SLA printing, and both edges were rounded with a 0.2 mm radius to enhance its strength.

3.2.6 Mechanical Design

Weiss cites both an experimental kW scale SLA resin air turbine and SLA diffuser vanes in operation [21], demonstrating that the material is suitable for this application. This was the chosen material in this thesis due to cost and manufacturing simplicity.

The shaft, bearing and bracket arrangement is designed with the exact same principles used in the pump mechanical design as discussed in section 3.1.3. The new component is the turbine blisk and the stator as shown in fig. 21.




Figure 20: CAD Blade profile




Figure 21: Labeled CAD isotropic and section view of the turbine assembly

Due to being manufactured through SLA printing in Formlabs Tough 2000 resin, the turbine blisk was low in stiffness and the cantilevered blades were prone to deflection. To mitigate this, an integrated shroud was placed above as a ring to stiffen the blades and reduce tip deflection. FEA also showed that the deflection would bend the turbine disc and cause the blades to contact the stator, so counterweight blocks were added to the other side of the disc to balance this and reduce the bending.

The stator was designed in two halves so that it could be manufactured traditionally using 2.5D CNC milling. This necessitated a seal between the two halves. A 0.5 mm thick silicone gasket lasercut to be compressed between the two halves was used to seal the stator. The stator halves were then bolted by 8 M6 screws and 2 M4 screws to provide enough clamping force to compress the gasket and seal the stator against the design supply pressure of 7.65 bar. The bolts had to be distributed evenly around the stator to avoid gasket gapping and prevent leakage.

4 Experimental Setup

The experimental setup was designed for three specific configurations: Electric motor driven pump testing, Isolated turbine coupled to a hysteresis brake, and integrated turbine and pump testing.

4.1 Test Configurations




Figure 22: The three test configurations. In each case the TM306 torquemeter sits between the driving component and the load, so torque is measured at the shaft.

In all three configurations, there is a driving component, the torquemeter and a load. fig. 22a shows the electric motor driven pump testing configuration. The electric motor test is used to gather most of the data because the motor is more controllable, repeatable and safer. In this configuration. The second configuration in fig. 22b connects the turbine to a hysteresis brake to test the turbine in isolation. Due to time constraints, this configuration was not tested. The final configuration in fig. 22c connects the turbine and pump together to test the performance of the integrated system.

4.2 Mechanical Layout and Shaft Train

At the design 20,000 RPM for the rig, shaft alignment, rigidity and maintainability were the main drivers. At 20,000 RPM, available shaft couplers had barely any tolerance for misalignment. The Magtrol MIC-5-2470 couplers had a maximum 0.8mm axial, 0.36mm radial and 0.7° angular misalignment tolerance at 35,000 RPM. Shaft couplers had to be used to connect rotary components to the transducers, a requirement that doesn't have to be satisfied by turbopump units as the shaft can be machined as a single piece.

The central component of each configuration in fig. 22 is the Magtrol's TM306 inline torquemeter as it allows the stated $< 0.1\%$ torque measurement accuracy. As the torquemeter was designed to be mounted onto a base plate, a base plate design was chosen instead of an integrated assembly like a normal turbopump.

The base plate is a 20 mm plywood with a laminate on both sides to be semi-waterproof, to have a flat surface for mounting, rigid but also cheap. M6 and M8 Countersunk holes were drilled into the base plate with a CNC router to allow for precise mounting of the components.

Each rotating component sits on its own mount bolted down to this baseplate. The mounts were 3D printed with a flat rectangular base and the same 80.00 mm shaft height as the torquemeter, so that bolting a mount flat to the baseplate already puts its shaft on the torquemeter centreline in the vertical direction without any shimming. The mounts also carry the alignment reference faces described below. The whole turbomachinery stand is then surrounded by a blast shield, a frame of aluminium extrusion carrying a 20 mm Dyneema panel on the faces looking at the rotating parts and a 15 mm polycarbonate window where the test has to be watched. The frame is bolted to the bench rather than to the baseplate, so that a failure of the rig does not feed straight into the shield through the same structure. The sizing of these panels is the subject of the protection system design later in this chapter.

4.2.1 Shaft alignment

The reason the shafts had to be aligned was because flexible shaft couplers were used. These tolerate some misalignment at high speeds, an essential requirement for a test rig where two or more shaft have to be mechanically connected.

The alignment of each component to the torquemeter had many challenges. Mounting magnetic dial indicators onto the shafts was not possible due to three reasons. The shafts were made of austenitic stainless steels so they were non-magnetic, the shafts were short and had a low diameter (10-15mm diameter, with maximum stub length of 20mm). A short stub length is highly desirable in rotordynamics to increase rigidity and increase the first critical speed.

The shaft couplers were also single piece, so the shaft couplers which do not have a edge true to the shaft axis. This meant that the shaft couplers could not be installed after the shafts were aligned, as the couplers would have to be installed before the shafts were aligned. The space the shaft couplers took up meant it was even more difficult to use the shaft stubs for alignment.

It was decided to use the flat faces of the torquemeter base as the reference for alignment. By designing the pump and turbine mounts to have a similar rectangular base and assuming that each shaft was true to the rectangular base, alignment was finally possible. Angular alignment was achieved by 3D printing a spacer with two parallel edges for the pump or turbine to sit flat against onto the torquemeter. Then, radial misalignment was achieved by designing the face parallel to the shaft to be the parallel to the torquemeter face. A straight edge could then be used as a guide to align the shaft while tightening the mounting bolts. The usage of this alignment block is shown in fig. 23.

As the TM306 torquemeter's shaft with its riser was machined to be precisely 80.00 mm from the base plate, this same height was built into the pump and turbine mounts to achieve radial alignment in the vertical direction.




Figure 23: Shaft alignment procedure using the flat faces of the component mounts.

4.3 Water Circuit

The water circuit is as follows: A water tank is pumped by the supply pump into an inlet throttle valve then into the experimental pump inlet. The pump outlet is then throttled by an outlet throttle valve before being returned to the water tank. Pressure sensors are placed at the inlet and outlet of the pump to measure the head rise across the pump. Flow rate is measured by a flow meter placed in the inlet line before the inlet throttle valve instead of the return line due to space constraints placed by the blast shield.




Figure 24: P&ID of the water circuit for the electric motor driven pump test configuration.

4.3.1 Inlet and Outlet Throttle Valves

The inlet throttle valve allows a reduction in pump inlet pressure to characterise the cavitation behaviour of the pump. The outlet throttle valve allows for a reduction in flow rate to characterise the head and cavitation behaviour of the pump at different flow rates.

The selection of the size of the inlet and outlet valves are crucial to the quality of the data. Ball valves were chosen as there were spares available, and they could be throttled in a controllable and repeatable manner by the angle of the valve handle. Custom 3D printed housings were designed to attach a servo motor to the valve handle in direct drive to allow for precise, remote and repeatable control of each valves.

Valve capacity is expressed throughout with the flow coefficient K_v , defined by

$$Q [\text{m}^3/\text{h}] = K_v \sqrt{\frac{\Delta p [\text{bar}]}{SG}} \quad (52)$$

where SG is the specific gravity of the fluid, 1 for water. Measuring the flow rate and the pressure drop across a valve at a known opening angle therefore measures its K_v directly, which is how the characterisation below was done.

The main requirement for both valves were so that the range of required flow rates and pressure drop through each valve corresponded to a large range in valve opening angles. For the inlet valve, fully open must have a large margin to the cavitation limit of the pump, ideally, cavitation would start at around 50% valve opening and could be further reduced until the valve is closed. For the outlet valve, fully open must be at least 1.5 times the cut-off flow rate of the pump.

This requirement is further driven by the $1 - 3^\circ$ resolution of the servo motors available in the department. Data for K_v against opening angle were extrapolated from online data from $1/8''$ in to $3/4''$ in were studied. However, as the data was extrapolated from data of ball valves with larger diameters, they had to be experimentally validated. The flow through a ball valve is also highly dependent on inlet and outlet conditions such as contraction or expansion of pipe diameter at the ports [?]. The size of my pipes were limited to what I could find in spare drawers, adding to the uncertainty.

fig. 26 shows the experimentally measured K_v against opening angle values were lower than expected. However, this worked in my favour as it actually increased the range of useful valve opening angles.

The location chosen for the experiment required a safe test area and a control room separated to allow for the failure of the test rig without risk to the operator. For this reason, the experiment was conducted within the Imperial College Hypersonics Lab. The test room contains equipment that had to be protected, so a blast shield was designed and set up around the turbomachinery stand to protect the equipment from the possibility of mechanical failure and fragmentation.

4.4 Air supply

Originally, a 100 bar compressed air supply was designed and parts readied to be used to drive the turbine. Unfortunately due to time constraints, the shop air supply within the hypersonics lab was used instead. Details of the 100 bar compressed air supply can be found in . The shop air which was limited to 7 barg was connected to partially assembled parts of original feed system. The shop air was connected to a GRT20s-280N100-SSKN-L 0-280 to 0-100 bar regulator with a K_v of 1.5. This regulator fed into the the main $1''$ valve, teed into a $1/2''$ vent valve and finally into the turbine inlet.

Both valves were Swagelok pneumatically actuated spring return ball valves. The main valve was the SS-65TS16-35C with a C_v of 40 and the vent valve was SS-45S8-33C with a C_v of 12. These valves were driven by




Figure 25: Servo driven throttle valve assembly




Figure 26: Extrapolated against measured valve capacity




Figure 27: P&ID of the water and air circuit for the turbopump configuration.

2 5/2 solenoid valves connected to the shop air supply.

Due to droop in the shop air regulator, maximum turbine inlet pressure at max flow was measured to be 3.1 bara.

There was no budget for an air flowmeter. A P&ID of the combined air supply and water circuit is shown in fig. 27.

4.5 Instrumentation and Data Acquisition

For cost and time reasons, a custom data acquisition and control system was designed to allow for remote operation of the test rig.

4.5.1 Main Architecture




Figure 28: Block diagram of full electronics system including safety, data acquisition, and control components.

The electronics system was designed to be enclosed in a plastic box placed in the test room, controlled by a LAN cable fed under the wall between the test room and the control room into my laptop. The main system architecture is shown in fig. 28.

fig. 29 shows the physical electronics box described by fig. 28. The main computer inside this box was a Raspberry Pi 5 running a backend written in Python. The Raspberry Pi communicated with 3 ESP32S3 microcontrollers over a UART serial connection at 921600 baud. One ESP32S3 was used as the actuator controller, one was used as a ADC and flowmeter DAQ, and one was used as a thermocouple DAQ. Breadboards would require too many wires to maintain and unstable, while there was not enough time to make custom PCBs. Soldered perfboard was used to connect the components. The Raspberry Pi communicates through the LAN cable through UDP to a laptop in the control room, allowing for live data readout and control of the test rig with a GUI written in Python and Qt.




Figure 29: The electronics box with the Raspberry Pi, ESP32S3s and power supply.

4.5.2 Power Architecture and Custom Boards

Power in this electrical system is separated into logic and actuation power as shown in fig. 28. Logic power is designed to be always powered on to allow the operator to have live readout of the system at all times, while actuation power is designed to be switched on only during a test for safety reasons with a dual redundant emergency shutdown (E-Stop) system.

Most components in the electronics system were powered by a DC 24 V 1.2 kW power supply. The high power supply was chosen as it was a simple way to power the electric motor without the use of batteries.

4.5.3 Electronics Safety Design

Safety was the top priority in the design of the electronic system, and all safety design relies hardware implementation instead of software. The core component is a PILZ PNOZ X3 safety relay wired as a dual channel redundant switch. The control room E-stop button is dual-channel, and the safety relay is designed to be fail safe against relay contact welding. An overspeed trip alarm by the DSP6001 is wired to open one of the two channels if the overspeed is detected. Once tripped, the relay then cuts the supply to every actuator. These include solenoid valves, electric motors, servo valves and the supply pump.

4.5.4 ADC Measurements

Pressure, torque, RPM, voltage and current were measured with a MCP3208 8 channel 12-bit ADC connected to the ESP32S3. The MCP3208 was powered by a LT3042 LDO at 5.11V to reduce noise. This 5.11V was also used to power the pressure sensors. As the pressure transducers were ratiometric, both the ADC and the pressure transducers track back to the same voltage reference, reducing drift and noise.

The custom backend could only send UART signals back and forth to the ESPs at a 50 Hz loop. The MCP3208 was capable of sampling up to 100 ksp/s, so the ESP32 was programmed to collect 32 samples and average them per channel before sending the averaged data back to the Raspberry Pi. High frequency data couldn't be collected due to the UART connection being the bottleneck, but this averaging allowed for measurement of voltage at a resolution higher than 12-bits. For uncorrelated noise the averaging reduces the standard deviation of each logged point by eq. (53), which is a factor of about 5.7.

$$\sigma_{avg} = \frac{\sigma}{\sqrt{N}} = \frac{\sigma}{\sqrt{32}} \quad (53)$$

Originally, a separate computer running Magtrol's M-Test software was planned to be used to read the torque and RPM from the DSP6001. However, by connecting the DSP6001's analog output for torque and RPM to the MCP3208, the torque and RPM data could be integrated into the same DAQ system as the pressure sensors, allowing for time-exact data synchronisation and simpler data collection.

To measure the torque and RPM, the TM306 torquemeter was connected to the Magtrol DSP6001 dynamometer controller. The DSP6001 outputs a -10V to 10V analog signal for torque, and 0 to 10V for RPM. The DSP6001 was set to output 1V per 0.25 Nm and 1V per 5000 RPM. Because the MCP3208 could only measure positive voltages, an OPA2134 op-amp was used to shift the expected -5V to 5V torque signal to 0V to 5V. As the op-amp was not rail-to-rail, a buck converter was used to generate a -9 V and +9 V supply for the op-amp.

The motor's voltage and current were also measured by the ADC. The 24V supply to the motor ESC was measured with a voltage divider, and the current was measured with a WCS1600 DC hall effect current sensor.

4.5.5 Other sensors

K-Type thermocouples although are less accurate for such a small temperature range were chosen for their cost. The thermocouples were read by an Adafruit MAX31855 thermocouple amplifier breakout board with integrated voltage regulator connected to the ESP32S3.

A E-WFS-GE turbine flowmeter with a range of 2 to 45 L/min with a cited accuracy of $\pm 10\%$ was used. To calibrate the flowmeter, a bucket and stopwatch was used to compare the flowmeter to the integrated flow rate over a period of time. The flowmeter was found to be accurate to $\pm 3\%$ [?]. The turbine generates pulses based on its rotation rate. The ESP32 measures the interval between these pulses to calculate the flow rate.

4.5.6 Actuator Control

One ESP32 is dedicated to actuation so the sensing loop is never held up by driving the actuators. It commands the two servos on the inlet and outlet throttle valves, holding each valve angle to the resolution the servo allows, and it drives the two solenoid valves that pilot the Swagelok pneumatic ball valves on the air side. All of this actuation power runs through the PILZ safety relay, so a trip or any loss of power drops every actuator to its safe state, the throttle servos going limp and the spring return air valves closing the supply and venting the manifold.






Figure 30: The interior of the electronics box showing the ESP32S3s and perfboard.



(a) Attempt at freezing bubble motion with a short exposure time, but the rolling shutter distorts the image.



(b) Lighting placement for dark field illumination, enhancing bubble visibility.



(c) Synchronized timestamp display for video-data alignment.

Figure 31: Cavitation imaging arrangement

4.5.7 Cavitation Imaging

The transparent front casing and diffuser allow cavitation to be observed under certain conditions. As bubbles are transparent, the imaging and lighting arrangement is crucial to cavitation visibility and quality. The casing was lit 90 degrees to the camera axis with a high intensity 70W LED as shown in section 4.5.7, so that bubble interfaces scatter light toward the camera while the bulk water and background remain dark. The color of the PLA behind the impeller was deliberately printed in black so that it absorbs the light, letting only the bubbles scatter it back to the camera.

The bright LED was used so that the camera could be set to a very short exposure time and attempt to freeze the motion of the bubbles. However, it was found during testing that the consumer phone camera that was used had a rolling shutter sensor. This means that even with the tested short exposure time of $1/19500$ s, each row of the camera's sensor is exposed at a slightly different time, so fast moving structures appear geometrically distorted as shown in section 4.5.7. There are two ways to improve this. The first is to use a global shutter camera, which exposes the entire sensor at once. The second is to use the LED in a strobe mode, flashing the light for microseconds with the camera's exposure time set to a longer value. This way, the camera sees only the strobe flash and the motion is frozen. This could have been possible by using the mosfet controllers on the actuator board to drive the LED in strobe mode. However, due to time constraints this was not implemented and is left as a possible future improvement to the experimental setup.

The setup was still useful for the purpose of identifying where and when cavitation occurs, which is arguably more important than getting a perfect image of the bubbles. To synchronize the video with the data, a 12 digit 7-segment display was placed in the camera's field of view, showing the backend's internal experimental timestamp as shown in section 4.5.7.

4.5.8 Instrument Uncertainty

table 4 lists every measurement channel with its range and two separate uncertainty figures. The first is the datasheet specification, the worst case the manufacturer guarantees. The second is the uncertainty I actually achieved after calibrating the channel in place. Both feed the uncertainty analysis of section 5, where the systematic term is combined in quadrature with the per point random scatter.

Most of the sensors are cheap, so their datasheet specifications are loose. The pressure transducers are rated at 3% of full scale (0.36 bar on the 12 bar range) and the flowmeter at 10% of reading. Calibrating each one against a better reference tightens it substantially, by up to an order of magnitude on the pressure channel. The transducers were calibrated against a digital gauge to ± 0.01 bar and the flowmeter against a timed bucket fill to $\pm 3\%$. The pressure transducers however drift with temperature. Each pressure transducer is zeroed to ambient temperature before each test, but when water is flowing the transducer cools and the zero drifts to a measured ± 0.05 bar, which is the uncertainty used in the analysis.

The TM306 is the best rated sensor in the rig, with a quoted accuracy of $< 0.1\%$ of its 5 Nm range. Using the DSP6001's analog output brings it to $0.02Nm$ but this loss in accuracy was traded for the convenience of having all channels in the same DAQ system.


The thermocouple is the one channel I could not recover. Its calibration drifted during testing, so the temperature data was discarded and water properties were taken at an assumed ambient value. Temperature does not enter the head or efficiency results, so this only affects the vapour pressure term in the cavitation analysis, where its contribution is small.

Table 4: Measurement channels, ranges and systematic uncertainties.

Quantity	Sensor	Range	Output	Datasheet Unc.	Measured Unc.
Pressure	DC5V 1.2MPa	0 to 12 bar	0.5-4.5 V	3% F.S.	0.05 bar
Flow rate	E-WFS-GE	2 to 45 L/min	Pulse	$\pm 10\%$	$\pm 3\%$
Torque	TM306	-1.6 to 1.6 Nm	0-5 V	$< 0.1\%$	0.01 Nm
Shaft speed	TM306	0 to 20,000 RPM	0-5 V	$< 0.1\%$	5 RPM
Temperature	K Type TC	-200 to +1300 °C	MAX31855 output	$\pm 2^\circ\text{C}$	N/A

4.5.9 Electric Motor Drive and Control

A hobby 4 pole 4092 800 Kv brushless DC motor was used to drive the pump. The motor was controlled by a spare unbranded 80 A 6S electronic speed controller (ESC). To mount this motor to test rig, a single piece PLA 3D printed bracket was designed to hold and align the motor to the torquemeter's shaft in the same way as the pump and turbine mounts. Both the motor and the ESC can be seen in the left of the fig. 32. Both the ESC and motor consume a lot of power, so cooling solutions were used for both of them. The motor was equipped with a water cooling jacket fed by the water circuit, while the ESC had a fan mounted to the top of its radiator.

**Figure 32:** The electric motor and ESC mounted to the test rig.

The ESC was powered by the 24 V supply from the electronics box through a contactor driven by a mosfet on the actuator board connected to the safety relay. The system was sized to allow motor driven testing up to 1.2 kW, the maximum power the power supply could deliver. However, during testing it was found that the ESC could not deliver more than 0.45 Nm of torque to the motor, which limited the maximum speed during motor driven pump testing to 9000 RPM at zero flow, which is the lowest torque condition of a pump. During useful experimental testing requiring flow, the maximum characterised pump speed where the ESC did not repeatedly fail was capped at 7500 RPM.

The plan was to use this cheap ESC to test the low power and low speed operation of the pump, and then to upgrade to a more expensive and robust ESC driven by batteries as batteries can deliver more current than the power supply. The cheap ESC had a very low $\approx 60\%$ electrical to mechanical power conversion efficiency as measured by voltage and current against the torque and speed. All of these limitations meant that a maximum of 600 W of electrical power was delivered to the ESC during testing, and a maximum of 400 W of mechanical power was delivered to the pump, which is well below the 1.2 kW that the system was sized for.

A replacement ESC was purchased and installed onto the test rig, however it unfortunately arrived defunct before experimental time ran out and thus the motor driven pump testing was limited to 7500 RPM.

5 Results and Discussion

5.1 Experimental Campaign

The experimental campaign was conducted in three phases: commissioning, electric motor driven pump testing, then integrated turbine and pump testing. The standalone turbine testing was not conducted due to time constraints. This means the turbine is assessed through its models and through the coupled test, and a standalone brake characterisation is the first item of future work.

5.2 Electric Motor Driven Pump Testing

Following objective 1 of the thesis, which is to characterise the head-flow, efficiency and cavitation characteristics, a series of runs were conducted with the pump driven by the electric motor. Five high quality runs were conducted at different motor throttle settings, providing a range of shaft speeds up to 8500 RPM. The head flow curve and cavitation characteristics require different testing profiles.

1. To measure the head-flow curve, the outlet valve was swept from fully open to fully closed slowly while the inlet valve was held open to supply the maximum inlet head possibly by the supply pump. This also measures the efficiency curve.

2. The cavitation characteristics are determined by the minimum inlet pressure before head breakdown or the NPSH required of the pump at different flow rates. This was measured by sweeping the inlet valve from fully open to fully closed at different outlet valve angles.

To speed up data collection, these two tests were combined into a single sequence of valve commands, run at different motor throttle settings. The exact test profile is:

1. T+0: Motor throttle is set to a fixed value, outlet valve is fully open 0° , and the inlet valve is fully open 0° . The outlet valve then starts closing slowly over 20 seconds.
2. T+20: At this point, the outlet valve is fully closed. It is then slowly opened to 10° .
3. T+25: Once the outlet valve is at 10° , the inlet valve is swept from fully open to fully closed over 20 seconds.
4. T+45: The inlet valve is fully closed, and starts opening back up to 0° over 5 seconds.
5. T+50: The outlet valve is stepped to 20° and the inlet valve is swept again from fully open to fully closed over 20 seconds.
6. This repeats until the outlet valve is fully closed at 80° , where the inlet valve is swept one last time from fully open to fully closed over 20 seconds and the test ends with both valves commanded to fully open again and motor shut down.

Figure 33 shows the raw channels for all five runs laid over each other against time, the outlet pressure, the flow rate, the shaft torque, the speed, and the two valve positions. Each run is a single ESC throttle setting, displaying the whole electric motor driven pump campaign off this one figure. The two valve rows are the test procedure itself. The two valve traces fall on top of each other across all five runs because the sequence was scripted and identical every time, so any difference between runs comes only from the motor throttle setting.

The first thing the data shows is that everything moves together in the direction it should. A higher throttle setting gives a higher steady speed, and the runs separate cleanly from around 3500 to 7500 RPM with no overlap. The outlet pressure, the flow and the torque are all ordered by speed in the same way, the fastest run highest on every channel and the slowest lowest, and none of them cross over. Within the H-Q test (first 20 seconds of each run) the pressure and the flow move in opposite directions, as the outlet valve closes the pressure rises and the flow falls, which is the head flow trade-off that a pump curve summarises shown directly in time before any curve is drawn [41]. Every channel responds to each valve action coherently, pressure rising as flow falls and torque tracking the load, with nothing flat or lagging or fighting the others, which is the first sign that each sensor is behaving and that the runs are clean enough to compare.

The main limitation of the rig is visible straight away, which is that the shaft speed is not held constant through a run. In a standard head flow test the pump is driven by a closed loop speed controller where the speed is held relatively constant while the discharge valve is swept, so the measured curve belongs to one fixed speed [5, 36]. Here the pump is driven open loop by a brushless ESC that sets throttle rather than speed, so the pump shaft speed depends on the motor torque speed curve and speed drops whenever torque is increased. The consequence is that a constant speed characteristic cannot be read straight off the traces.

A second limitation is that all of this happens far below the design speed. The fastest H-Q run reaches about 7700 RPM, roughly a third of the 20,000 RPM the pump was designed for, so every measurement is off design.

The cavitation part of each run carries its own limitation that the raw data makes obvious. During every inlet sweep the flow drops as the inlet valve closes, which is the flow row dipping in step with the inlet valve, because the single inlet valve lowers the suction pressure and the flow at the same time. A dedicated suction test holds the flow constant while only the suction pressure is reduced [5, 42], so the coupling here means the pure suction behaviour at a fixed flow cannot be isolated and the breakdown has to be defined against a moving reference rather than a fixed one.

Finally the pressure and flow traces are noticeably noisy. This is not a measurement artifact. Rather, the scatter is consistent with partial emission operation, where the impeller blade gets near the outlet the velocity slightly increases. This is a known source of pressure unsteadiness in this kind of pump [18]. As Barske explains, altering the number of impeller blades can reduce this fluid vibration. It also means a single sample cannot be trusted the data has to be processed to remove the noise.

Finally, the torque is not zero at standstill. This is caused by the mechanical seal's static friction producing a torque against the motor's rotor and stator trying to reach equilibrium. While spinning, this effect is removed, so the this oddity can be safely ignored.

5.3 Data Processing and Uncertainty

To use the raw data to fully characterise the pump at the tested operating conditions, the data has to be processed to remove many effects. First of all, only the points above 75% of the run's median RPM and throwing away the spin up and spin down. Because the open loop drive lets the speed drift by around 8% over a single ramp, every surviving




Figure 33: Raw electric pump driven pump experimental data over 5 different motor throttle settings

point is then corrected back to the median speed which becomes the run reference speed through the affinity laws as described in section 2.1.3. The head scaled as the square of the speed and the flow scaled linearly with it [43]. This is the step that turns a run with a drifting speed into a clean characteristic at one reference speed, and it is what makes the five runs in fig. 33 comparable to each other, to the design point and to literature.

The pump is partial emission so the corrected traces are still noisy, around 2% scatter on head, which is close to the 3% cavitation breakdown the analysis has to resolve, so no single point can be trusted on its own. To handle this the corrected data are binned in flow, 28 bins for the head curves and 20 for the cavitation sweeps, and within each bin I take the median rather than the mean so that an occasional spike or dropout does not drag the point with it. The scatter that survives the binning is carried as the random uncertainty, taken as the standard error of the median, $1.253 \sigma / \sqrt{n}$. This binning pulls the 2% raw scatter down to under 0.1 m on head, well below the 60% head collapse that marks breakdown, so the breakdown is a clear cliff and not lost in the noise.

The binned head and flow points, together with the reference speed and the impeller geometry, are then formed into the quantities the rest of the chapter plots. The head and flow are made non dimensional as the Gulich head and flow coefficients, $\psi = 2gH/u_2^2$ and $\phi_2 = Q/(\pi d_2 b_2 u_2)$ [5], which is the collapse in fig. 34. The shaft torque and speed give the input power and the overall efficiency $\eta = \rho g Q H / \tau \omega$, binned in flow the same way, which is fig. 35. The suction sweeps are reduced against the inlet pressure to give head against available NPSH and the 3% breakdown point, which is fig. 39. So the single set of raw channels in fig. 33 feeds every derived figure that follows, through one reduction rather than three.

On top of the random scatter each measured quantity also carries a systematic uncertainty from its instrument, the values listed in table 4. The error is propagated with the `uncertainties` python package. The random and systematic parts are then added in quadrature and the error bars are drawn at twice the combined standard uncertainty, so they are roughly 95% intervals.

5.4 Pump Head-Flow Characteristics




Figure 34: Dimensional and non-dimensional head-flow curves, with two Lock model curves overlayed.

fig. 34 Shows the actual achieved head rise across flow rates at the different RPMs that were tested. Overlayed are solid and dashed lines. Both are theoretical head-flow curves generated from eq. (27). The dashed line is with exactly the parameters from Lock’s paper, and the solid line is with the pre-rotation K_1 increased from 0.17 to 0.53. The dashed vertical dashed line shows the point at a synchronized video camera detected cavitation within the diffuser through the transparent diffuser wall. It can be seen that the original parameters overpredict the head rise, and there are many mechanisms that could be causing this.

The non dimensional head-flow curve shows the a clear validation of pump theory. The five speeds collapse onto a single curve at a head coefficient of $\psi = 1.10 \pm 0.05$ in the operating region, against a design value of 1.065, so the pump delivers its design head with around 3% to spare. The collapse itself is the experimental proof of dynamic similarity, and it is what licenses the affinity adjustment within runs and the extrapolation to higher speeds later in this chapter. The diverging tails at high flow coefficient are a rig artifact rather than a breakdown of similarity, because the fixed feed pressure means the maximum achievable flow coefficient falls as speed rises.

The difference between the theoreetical Lock model and the fitted curve was done by changing the pre-rotation constant K_1 and the diffuser loss coefficient ζ_D . In Lock’s own paper [16], he uses pre-rotation factors of around 0.15 to 0.20. However, he does not give any guidelines for this number. It might be unphysical to attribute the loss

of predicted head by prerotation, as in his paper he notes that a rounding of the rim blade leading edges reduces effective head. This could be another mechanism by which the predicted head was lower than the measured. The lack of modelling this rounding is a limitation of the model that needs to be addressed. The diffuser loss of 0.42 against the clean pipe entry value of 0.194 could be more consistent with literature. Gulich suggests that a rounded diffuser mouth induces recirculation, exacerbating diffuser loss. Even Lock states himself that the entry to the nozzle is very unfavourable.

The most important feature of fig. 34 is the high flow cutoff. Data shows great agreement between actual cavitation being detected by the camera made possible with the transparent casing. On every head flow ramp the video shows cavitation in the diffuser throat clearing as the flow falls, frame matched to the data at three flow rates across three runs. In the model, Lock's vapour pressure cutoff lands on all three video clearing points to within roughly 10%.

5.5 Pump: Efficiency and Churning

The overall efficiency is computed from eq. (54).

$$\eta = \frac{P_{hyd}}{P_{shaft}} = \frac{\rho g Q H}{\tau \omega} \quad (54)$$

The efficiency curve generated by measuring shaft power, subtracting mechanical losses can be shown in the following graph:




Figure 35: Pump efficiency and the churning measurement.

The right graph shows the predicted efficiency curve from pure theory, and the right graph shows the curve but with adjusted disc friction. To explain the disc friction adjustment, the pump data at zero flow where all the shaft power was only going into hydraulic losses. fig. 35b shows that the measured disc friction losses are about 2.5 times higher than Barske's formula ??for disc friction. Adjusting the disc friction by this factor leads to a much better fit of the efficiency curve, as can be seen in fig. 35a.

The discrepancy between the theoretical efficiency and measured efficiency was predicted due to looking at at flow shutoff measurements. As zero flow, there is no output power. After subtracting the measured mechanical losses, everything the shaft delivers goes into churning the flooded casing. Across 15 shutoff points from 2,800 to 8,500 RPM the measured churning sits at 2.5 to 2.9 times the Barske disc correlation, with a mean of 2.54, and follows a power law of $n^{3.1}$, between Barske's exponent of 2.8 and the cubic forms in Güllich. The factor of 2.5 used in the efficiency model was originally fitted to the efficiency curves, so its agreement with the shutoff measurement is corroboration by data that did not produce it.

5.6 Pump: Extrapolation to Design Speed

As the pump was only tested to a third of its design speed, the predicted efficiency at the design speed has to be extrapolated from the test data. Following a scaling that was done by NASA in a test of a larger pump of a low specific speed rocket pump took the efficiency from 58.7% to 68.9% [9], the five runs can be used for extrapolation. fig. 36 plots the peak efficiency of each run against speed and fits the loss ratio model $(1 - \eta) \propto Re^{-a}$, which is the standard form for friction dominated loss scaling. The fitted exponent is $a = 0.098 \pm 0.010$, essentially the textbook Moody value of 0.1, and extrapolating along the fit gives an efficiency of 26.4% at 20 000 rpm with a band of 25.7 to 27.1%. The exponent is measured from this machine, not assumed, which is the difference between an extrapolation and a guess.




Figure 36: Peak overall efficiency per run against shaft speed, with the fitted loss ratio $(1 - \eta) \propto Re^{-a}$ and its uncertainty band extrapolated to the design speed. The fitted exponent $a = 0.098 \pm 0.010$ matches the textbook friction scaling.

Comparing the measured efficiency of 19% and extrapolated 26% to literature shows that the pump here performed at a lower efficiency than CFD predicts. Knyazeva [6] gives a CFD simulated barske pump of specific speed $n_q = 4.7$ at 31% efficiency. Danieli[8] reports that his CFD results for specific speed 9 barske pump gets up to 63%. Kim’s closed impeller design at the same n_q reaches 67% in CFD, but it is unvalidated and requires 0.31 mm closed channels [7]. Historic measured partial emission pumps from SP-8107 [22], Balje [1] and [44] sit at 35 to 60% at much larger scale. The gap between this machine and those numbers might be accounted for by the measured churning and the lower Reynolds number, or it could also be an unexplained deficiency in the design.

Carrying the churning multiplier of 2.5 unchanged to 20 000 rpm would predict around 3 kW of churning alone, more than the entire turbine power budget. At higher reynolds numbers, this multiplier should fall, and the extrapolation of efficiency to design speed is a more realistic estimate of the machine’s performance. The measured churning multiplier is a useful data point for future work, as it is a direct measurement of the open impeller architecture’s cost in this machine.

5.7 Pump: Cavitation

Cavitation behaviour matters a lot for a rocket pump, since the whole point of the feed system is to run the propellant tanks at low pressure, so the pump has to tolerate a low inlet head without losing its rise. This section characterises where this pump breaks down and, more interestingly, what part of the pump actually causes it.

The suction test is run by holding the speed and the flow rate, then closing the inlet throttle to walk the inlet pressure down. fig. 37 shows the result, one curve per held flow rate, head normalised by the nominal operating head against the NPSH available. Each curve holds its reference head over most of the suction range and then falls off a cliff. The 3% head drop criterion picks the breakdown point off each curve, and because the cliff is steep the choice of criterion barely changes the result.

The low flow curves do this cleanly, holding their reference head over most of the suction range and then falling off a cliff. The high flow curves instead climb as the inlet pressure comes down, the highest flow run reaching about 2.4 times its reference head before the same cliff. That climb is an artifact of the test setup. As closing the inlet throttle also lowers the flow rate, there is around a 34% drop over a sweep in the higher flows. As seen in ??, decreasing flow rate near the cutoff point leads to a higher head, so each curve is the head flow characteristic walked backwards as the valve shuts. A standard suction test would hold the flow fixed and RPM fixed and lower only the inlet pressure, which this single inlet valve cannot do. To remove this effect from the data, each each point will have to be normalized against the non cavitating head at its own flow taken from the measured head flow curve. Or, closed loop control to hold a steady flow rate while lowering the inlet pressure would be needed, which is left as future work.





Figure 37: Suction test curves at constant speed: normalised head against NPSH available, one curve per held flow rate, by successive reduction of the inlet pressure. The lines are smoothing splines fitted through them to show the trend. The horizontal line is the 3% head-drop criterion used for fig. 39.

Reading the breakdown point off every curve gives the NPSH required as a function of flow rate, shown in fig. 39. The dashed line is the theoretical cutoff from solving eq. (29) for the flow rate at which the head at the diffuser throat drops to the vapor pressure head. The measured 3% breakdown points sit close to this Lock throat curve.


5.8 Pump: Video Observations of Cavitation

Video footage of the 45 and 50 percent ESC throttle were the only ones with quality enough to see the cavitation through the transparent front casing due to an encoding issue with the earlier recordings. The good footage however showed very interesting results. The footage was frame perfect and synchronised to the backend clock to within plus or minus 0.03 seconds. I verified the synchronisation independently by matching the RPM start and stop transitions in the video against the logged data. Both the suction bubble formation and the throat onset can be tracked to frame accurate timing on these two runs. The 40 percent run was already degraded and most of its onset times had to be estimated, and everything below 40 percent was too poor in quality to read, so the analysis rests on the 45 and 50 percent runs with the lower throttles treated as supporting.


Watching the impeller eye, the cavity is not a single boundary but three concentric zones, read from the centre outward. There is a full air core in the middle, then a layer of bubbles, then an outer bubble edge that forms within milliseconds and marks the boundary against fully wetted water. The state at the eye moves through a clear sequence as suction pressure is lowered: nominal, with all water and no bubbles; onset, where a small bubble first appears against otherwise solid water; an intermediate state, where moving outward from the centre you pass from full air, through bubbles, to water; and full cavitation, where the centre is full air and the remaining annulus is only bubbles. Lowering the inlet pressure grows the cavity, so a lower inlet pressure corresponds directly to a larger bubble radius.




(a) Fully wetted



(b) Eye cavitation only



(c) Throat cavitation



(d) Both sites, near breakdown

Figure 38: Stills through the transparent front casing at descending NPSH. The eye cavitates first with no measurable head effect, while the appearance of throat cavitation coincides with the head breakdown. Frame timestamps are synchronised to the logged data.




Figure 39: NPSH at 3% head breakdown against flow rate, with the visually observed throat cavitation onsets and the Lock throat cutoff curve. Error bars as in fig. 34.

The 3% breakdown taken from the pressure data coincides with the visually observed throat cavitation to around 0.1 m of NPSH. From video footage, cavitation at the impeller eye appears far earlier in the test and does nothing measurable to the head.

The part that makes this more than a standard suction test is where the breakdown actually happens, and two independent methods agree on it. So the naive picture of pump cavitation, bubbles forming at the inlet eye and killing the head, is just wrong for this machine. The eye cavitates benignly and it is the diffuser throat that drives the breakdown. This is Lock’s diffuser limited claim, confirmed here and this time directly visualised through the casing.

One caveat on the method. The inlet throttle drops the flow rate as well as the suction pressure as it closes, so strictly the breakdown point is the knee of the cliff rather than a fixed reference percentage. Here the difference is small because the cliff is steep enough that the two definitions land in the same place.

Packaged as a single number that the literature can be compared against, the suction specific speed at breakdown is around 75 in metric form. That is close to the cavitation onset value of around 64 reported for a Barske type impeller in the same regime [6], and far below the industrial figure of around 200. The reason it is so low is the same finding as above: the throat sets breakdown, not the eye, so the usual eye-limited suction specific speed does not apply.

The throat sizing itself also lands somewhere interesting against the literature. The throat to tip diameter ratio of this pump is about 0.051, which follows the classical Barske and Balje guidance directly. That is the same starting point Danieli used for his partial emission rocket pump, whose initial throat ratio of 0.064 failed his head requirement, and his CFD optimisation only recovered the head and efficiency by opening the throat ratio out to 0.18 to 0.28 [8]. That independently corroborates the finding here that the classical throat under delivers and limits the runout, and it hands the design a clear future work item: enlarge the throat, traded off against the suction margin that partial emission buys. His flow rate is 2.7 times larger and his study is CFD only, so it is the trend being cited here, not the numbers.

5.9 Coupled Turbopump

The integrated test is the proof of concept of the whole project. With the turbine driving the pump on shop air, the shaft settled at around 5400 RPM, the pump produced a measurable head rise, and the assembly survived repeated runs. The settling itself is a result: the speed approached the match point monotonically and held it without any active control, which is the self regulating behaviour predicted by the torque matching argument of section 2. The operating point is deep off design, with the stator pressure at roughly 38% of the design supply and a blade to jet speed ratio of around 0.06 against the design 0.2. fig. 40 shows the coupled pump data landing on the motor driven curves, which is the cross validation between the two test configurations.




Figure 40: Coupled turbine driven pump operation against the motor driven characteristic curves. The coupled data, coloured by shaft speed, lands on the same head flow behaviour measured under motor drive.

The turbine side needs more care, because the rig has no air mass flow meter. Without a measured mass flow, a single forward efficiency number for the turbine would be under determined: a choked mass flow with a weak jet and a reduced mass flow with a near design jet both fit the same measured torque. Quoting one number would be misleading, so this thesis does not.

The torque models compared against the data in fig. 41 are built from the Euler equation with the choked mass flow of eq. (48), which remains valid regardless of the rotor state. For a rotor receiving an effective tangential jet

velocity c_{3u}^e , the shaft torque is

$$\tau = \dot{m} (1 + k_R) r_m (c_{3u}^e - u) \quad (55)$$

where the factor $(1 + k_R)$ carries the contribution of the turned relative flow at exit. The started model sets c_{3u}^e from the full design expansion at the measured supply pressure, while the unstarted model treats the effective jet as a fraction of it, fitted to the data.

What breaks the degeneracy is the starting analysis from section 3. At the test shaft speed the blade speed is so low that the rotor inlet relative Mach number rises to 1.58, above the Goldman starting limit of 1.408, so the rotor passages cannot swallow the startup shock system and the rotor runs unstarted. The design stage prediction was that the rotor cannot start below approximately 15 300 RPM, and the coupled test never exceeded half of that. An unstarted rotor sits behind a detached bow shock, the passage flow is subsonic, and the jet momentum reaching the blades collapses. fig. 41 shows the consequence: the measured torque of around 0.27 Nm sits a factor of four below the started flow model at around 0.87 Nm, and an unstarted model with an effective jet of around a third of the design velocity passes through the data. The near design jet branch of the degeneracy is ruled out precisely because it would require a started rotor, which the starting criterion forbids at this speed. The torque deficit is therefore not an anomaly, it is a diagnosed off design state that the design stage analysis predicted before the test was run.




Figure 41: Coupled shaft torque against speed: measured data, the started flow model (dashed) and the unstarted model with a reduced effective jet (solid with band). The factor of four deficit against the started model is explained by the rotor running unstarted below the starting threshold.

Two rigour checks defend this diagnosis. First, the nozzle can be ruled out as the location of the loss. At the test supply pressure the over expanded conical nozzle sits at a pressure ratio of about 0.61 to ambient, above the separation threshold of roughly 0.4 from the rocket nozzle separation criteria [45], so the nozzle remains attached and supersonic and the velocity collapse must happen at the rotor. Second, the threshold itself should not be over read. With three discrete nozzles the rotor relative Mach number varies around the admitted arc, so the 15 300 RPM figure is a mean flow estimate and operation near it may start and unstart intermittently [12].

Because the stage was never measured in its started state, the design point efficiency prediction has to lean on external evidence, and the literature provides a tight bracket. The closest comparison is a machine of the same architecture, a radial inflow supersonic partial admission impulse stage at Mach 1.65, where the measured debit from ideal efficiency was 28 percentage points [40]. The Weiss chain here predicts 65% falling to 0.47, a debit of just under 28 points, so the loss model magnitude is corroborated experimentally to about one percentage point on the same machine class, with the caveat that his rotor ran started. Peng’s 1.5 kW partial admission supersonic stage gives a CFD efficiency of around 42.5% [14], bracketing the prediction from below. NASA tested a Mach 2 stage from full admission down to 12.5% admission and found the full admission efficiency at 42.5% with the drop to 12.5% admission costing only around 5 points [46], which matters here because it acquits partial admission: at $\varepsilon = 0.15$ the admission penalty is modest, and the measured deficit belongs to the unstart, not the admission. Ohlsson’s closed form partial admission theory, inside whose validation range this turbine’s arc to chord ratio sits, composes with his low aspect ratio correlations to a literature only stage efficiency estimate of around 0.60 at his design speed ratio [24, 23], a second independent bracket. Finally, a precedent exists for exactly this failure mode: the SLA resin turbine Weiss cites also

maxed out below its design speed with the cause left unexplained [21]. This work supplies the diagnosis that precedent lacked, the combination of supply droop and rotor unstart.

5.10 Extrapolation to the Design Point

The design point of 20 000 rpm was not reached in testing, so every claim about it is an extrapolation, and the value of this section is being precise about which extrapolations are licensed and which are not. On the pump side the licence is the non dimensional collapse of fig. 34. Because five speeds collapse onto one head coefficient curve, the affinity laws demonstrably hold for this machine, and fig. 42 carries the pooled curve to the design speed, where it passes through the design point. The efficiency extrapolation rides on the fitted Reynolds exponent of fig. 36 and arrives at 26.4% with a stated band.




Figure 42: The pooled non dimensional characteristic carried to 20 000 rpm by the affinity laws, with the Lock model at design speed and the design point marked.

On the turbine side the claim has to be narrower. The coupled test ran at around 5400 RPM with the rotor unstarted, so the stage similitude parameters at design, the rotor relative Mach number and the blade to jet speed ratio, were never matched. What is validated are the speed independent pieces: the choked nozzle, the MoC profile generation against Goldman’s published case, and the starting criterion itself, whose off design prediction the coupled test confirmed. Two named gaps remain on the road to 20,000 RPM. First, the started stage efficiency of 0.47 is a corroborated prediction, not a measurement, and stays that way until a test above the starting threshold. Second, the working fluid: cold air at $\gamma = 1.4$ stands in for hot gas at around 1.2, which shifts the expansion and the starting margin.

5.11 Synthesis

table 5 collects the quantitative comparisons of this chapter in one place.

Table 5: Predicted against measured summary. Percentage differences are computed by the analysis pipeline from the same registry that supplies every number in this thesis.

Quantity	Predicted	Measured	Δ	Note
head coefficient ψ	1.065	1.10 ± 0.05	+3 %	Barske design vs measured (5-speed c
overall efficiency η at 20 000 rpm	23.4 %	27 %	+16 %	design estimate vs Re-fit extrapolatio
shutoff churning power	Barske disk correlation	$2.5 \times$	+150 %	measured at shutoff, 15 points
rotor-inlet relative Mach M_{w3} at test	1.408	1.58	+12 %	vs Goldman starting limit $\rightarrow$ unstart
coupled shaft torque	0.87 N m	0.27 N m	−69 %	started-flow model vs measured (unst

On the adequacy of the toolchain, the verdict is positive within stated limits. Lock’s model reproduces the head curve including its droop, and places the cavitation limited runout at the right flow once the as-built throat is used, so it is adequate for design stage screening of this machine class. The Barske sizing model delivered a pump that

meets its design head coefficient within 3%. On the turbine, the speed independent codes validated cleanly, and the loss chain prediction is corroborated externally to about a point, but the started stage remains unverified by this rig. The 1D and analytical toolchain was sufficient to design, predict and diagnose everything this project measured, and nothing in the data demanded CFD.

On the Barske architecture itself, the central question of the thesis, the data supports a measured verdict. The architecture does what it promises at this specific speed: it is manufacturable where the conventional impeller is not, it delivers its design head, and its suction behaviour is dominated by a single identifiable mechanism that a transparent casing can watch. The price is efficiency, with churning measured at two and a half times the textbook estimate eating two thirds of the shaft power at test speed. Whether around a quarter efficiency at design speed is acceptable depends entirely on the application, and for expendable small rocket stages where feed pressure mass dominates, it plausibly is.

One mechanical learning point belongs in the record. The first rig iteration used printed plastic load bearing shafts, which crept and failed under high speed loads, and the redesign moved every rotating load path to metal, a stainless pump shaft and an aluminium turbine shaft. Printed structural parts are acceptable for casings and blading at these loads, but not for shafts.

6 Conclusions

A small scale low specific speed turbopump, a Barske pump driven by a supersonic partial admission impulse turbine, was designed, built and tested, and its measured behaviour was used to answer the three objectives set in section 1.4.

Objective 1, pump characterisation. The Barske pump delivers its design head, with the measured head coefficient of 1.10 ± 0.05 sitting 3% above the design value and collapsing across five speeds, which demonstrates dynamic similarity. The peak measured efficiency is $(19 \pm 2) \%$, and the dominant loss was identified and measured rather than assumed: churning of the flooded casing absorbs about two thirds of the shaft power at test speed, at 2.5 to 2.9 times the textbook disc friction estimate, measured directly at shutoff. The cavitation behaviour was characterised and, through the transparent casing, visualised: the impeller eye cavitates early and benignly, while breakdown is driven by the diffuser throat, with the 3% breakdown and the visual throat onset agreeing to around 0.1 m. Against the design methodology, Lock's model reproduces the measured head droop and locates the cavitation limited runout once the as-built throat geometry is used, the affinity laws hold demonstrably, and the fitted Reynolds scaling carries the efficiency to 26.4% at the design speed with a stated band.

Objective 2, turbine design and model validation. The turbine was designed with a toolchain of MoC blade generation, the Sasman and Cresci separation check, the Goldman starting criterion with Colclough's empirical derating, and the Weiss loss chain, giving a predicted total to static efficiency of 0.47 against an ideal 65%. The standalone brake test was not performed, so the started stage efficiency remains a prediction, corroborated to about one percentage point by a measured machine of the same architecture. The starting criterion proved to be the load bearing piece of the toolchain, as its off design prediction explained the coupled test result.

Objective 3, integration. Coupled turbopump operation was demonstrated at around 5400 RPM, with the turbine driving the pump to a measurable head rise and the shaft settling at a stable self regulating match point with no active control. The gap to the design speed is explained by two named and quantified mechanisms, the supply pressure droop to roughly 38% of the design stator pressure and the predicted rotor unstart below approximately 15 300 RPM, rather than by any unexplained deficiency of the machine. Taken together, the coupled result shows the combined 1D and analytical toolchain is sufficient for design stage prediction of this class of machine, and no result in this work required CFD to predict or to explain.

Overall, this work provides an open, experimentally validated characterisation of a Barske turbopump at $n_q \approx 6.4$, including a measured loss breakdown and a direct visualisation of the cavitation mechanism that sets its operating limit.

6.1 Future Work

Each item below names the uncertainty it resolves.

1. Standalone turbine characterisation against the hysteresis brake, above the starting threshold of approximately 15 300 RPM. The configuration is built but was never run, and it resolves the single largest open prediction, the started stage efficiency of 0.47.
2. A 15 mm direct rigid coupler to unlock the full 20,000 RPM envelope of the torquemeter, removing the drive side speed limit on pump testing.
3. An enlarged diffuser throat, traded against suction margin. The measured throat limited runout and the published optimisation trend [8] both point at the same lever.
4. Hot gas generator products as the working fluid, closing the specific heat ratio gap between cold air at $\gamma = 1.4$ and combustion gas near 1.2, which also shifts the starting margin.

future work: the cavitation curve that Lock describes, which only been seen by slowly closing the outlet valve instead of what did what is slowly closing

5. A machined metal impeller, to isolate the contribution of the printed surface quality to the measured churning multiplier.
6. A full admission variant at larger diameter, to isolate the partial admission sector losses from the rest of the loss budget.
7. CFD of the as-built geometry with the measured boundary conditions, now that there is experimental data to validate it against, targeting the partial admission windage and the shock boundary layer interaction the 1D tools cannot resolve.
8. Global shutter imaging with a synchronised strobe through the existing transparent casing. The present consumer camera resolves the cavity envelope but not bubble dynamics, since the frame rate sits far below blade passing and the rolling shutter distorts fast structures; individual bubbles already appear in isolated frames, so the optical access is proven and only the camera limits what it can measure.
9. High rate burst logging on the pressure channels. The logged data are 32 sample averages at 50 Hz, so blade passing unsteadiness at several hundred hertz is unresolvable by design; short bursts at the ADC's native rate would resolve it without changing the architecture.

References

- [1] OE BALJE. Turbomachines - A Guide To Design, Selection, and Theory. John Wiley & Sons, New York, 1981.
- [2] L. J. Goldman. Analytical investigation of blade efficiency for two-dimensional supersonic turbine rotor blade sections. Technical Report NASA-TM-X-2095, NASA, 1970.
- [3] Liquid rocket engine nozzles. Technical Report NASA-SP-8113, July 1976.
- [4] S. C. Kacker and U. Okapuu. A Mean Line Prediction Method for Axial Flow Turbine Efficiency. Journal of Engineering for Power, 104(1):111–119, January 1982.
- [5] Johann Friedrich Gülich. Centrifugal Pumps. Springer International Publishing, Cham, 2020.
- [6] E. G. Knyazeva and Y. Klochkov. Design and fluid dynamics features of a low-flow high-head pump with barske-type impeller. E3S Web of Conferences, 320:04013, 2021.
- [7] Hye In Kim, Tae-Seong Roh, Hwanil Huh, and Hyoung Jin Lee. Development of ultra-low specific speed centrifugal pumps design method for small liquid rocket engines. Aerospace, 9(9), 2022.
- [8] Piero Danieli, Massimo Masi, Riccardo Tridello, Mario Pessana, Francesco Barato, and Alessandro Chiesa. Conceptual design of the electric pumps for the high-performance engine of a european lunar lander. In ASME Turbo Expo 2023: Turbomachinery Technical Conference and Exposition. American Society of Mechanical Engineers Digital Collection, 2023.
- [9] C. Macgregor and A. Csomor. Rotating and positive-displacement pumps for low-thrust rocket engines. volume 1: Pump evaluation and design. Technical Report R-8494-1-VOL-1, NASA, 1974.
- [10] Emanuel Boxer, James R. Sterrett, and John Wlodarski. Application of supersonic vortex-flow theory to the design of supersonic impulse compressor- or turbine-blade sections. Technical Report NACA RM L52B06, NACA, 1952.
- [11] L. J. Goldman and V. J. Scullin. Analytical investigation of supersonic turbomachinery blading. 1 - computer program for blading design. Technical Report NASA-TN-D-4421, NASA, 1968.
- [12] Samuel Sudhof. Development Techniques for Supersonic Turbines. PhD thesis, Technical University of Munich, 2020.
- [13] Lisa Griffin and Daniel Dorney. Design and Analysis of Turbines for Space Applications (Invited). In 33rd AIAA Fluid Dynamics Conference and Exhibit. American Institute of Aeronautics and Astronautics.
- [14] Ningjian Peng, Enhua Wang, and Wenli Wang. Design and analysis of a 1.5 kw single-stage partial-admission impulse turbine for low-grade energy utilization. Energy, 268:126631, 2023.
- [15] Ahmed M. K. Abdalhamid and Ahmed Eltaweel. Design and analysis of a single-stage supersonic turbine with partial admission. Energy, 309:133100, 2024.
- [16] Thomas Lock. A forced vortex pump for high speed, high pressure, low flow applications. SAE Transactions, 74:729–737, 1966.
- [17] U. M. Barske. Development of some unconventional centrifugal pumps. Proceedings of the Institution of Mechanical Engineers, 174(1):437–461, 1960.
- [18] U. M. Barske. The design of open impeller centrifugal pumps.
- [19] George Friedrich Wislicenus. Fluid Mechanics of Turbomachinery. McGraw-Hill Book Co., New York, 1st ed. edition, 1947.
- [20] Hydraulic Institute. Pipe Friction Manual. Hydraulic Institute, New York, 1954. Lock’s source for the diffuser loss coefficient $\zeta = 0.194$. Verify edition/year before final.
- [21] Andreas P. Weiß, Václav Novotný, Tobias Popp, Philipp Streit, Jan Špale, Gerd Zinn, and Michal Kolovratník. Customized orc micro turbo-expanders - from 1d design to modular construction kit and prospects of additive manufacturing. Energy, 209:118407, 2020.
- [22] Turbopump systems for liquid rocket engines. Technical Report NASA SP-8107, NASA, 1974.
- [23] Gunnar O. Ohlsson. Low aspect ratio turbines. Journal of Engineering for Power, 86(1):13–16, 1964. In Zotero (storage JJQF4B5G) – citekey guessed per BBT scheme; VERIFY against the final BBT export.
- [24] Gunnar O. Ohlsson. Partial admission turbines. Journal of the Aerospace Sciences, 29(9):1017–1024, 1962. PDF in Downloads (ohlsson1962.pdf) – import to Zotero, then move this entry to references.bib.

- [25] Liquid rocket engine turbines. Technical Report NASA SP-8110, NASA, 1974.
- [26] Arthur J. Glassman. Turbine design and application volumes 1, 2, and 3. Technical Report NASA SP-290, NASA, 1994.
- [27] Walter Traupel. Thermische Turbomaschinen: Zweiter Band Regelverhalten, Festigkeit und dynamische Probleme. Springer-Verlag, April 2013.
- [28] H. R. M. Craig and H. J. A. Cox. Performance Estimation of Axial Flow Turbines. Proceedings of the Institution of Mechanical Engineers, 185(1):407–424, June 1970.
- [29] C. D. Colclough. Design of turbine blades suitable for supersonic relative inlet velocities and the investigation of their performance in cascades: Part i-theory and design. Journal of Mechanical Engineering Science, 8(1):110–128, 1966.
- [30] Hermann Schlichting and Klaus Gersten. Boundary-Layer Theory. Springer Berlin Heidelberg, Berlin, Heidelberg, 2017.
- [31] Philip K. Sasman and Robert J. Cresci. Compressible turbulent boundary layer with pressure gradient and heat transfer. AIAA Journal, 4(1):19–25, 1966.
- [32] John David Anderson. Fundamentals of Aerodynamics. McGraw-Hill Education, 2017.
- [33] L. ERIKSSON. Development of a supersonic turbine stage for the hm60 engine. In 20th Joint Propulsion Conference. American Institute of Aeronautics and Astronautics.
- [34] A. Kantrowitz. The Supersonic Axial-Flow Compressor. 1950.
- [35] G. V. R. Rao. Exhaust Nozzle Contour for Optimum Thrust. Journal of Jet Propulsion, 28(6):377–382, June 1958.
- [36] Igor J. Karassik, Joseph P. Messina, Paul Cooper, and Charles C. Heald. Pump Handbook. McGraw Hill, New York, 2008.
- [37] Parker O-Ring Handbook. Technical Report ORD 5700.
- [38] SKF Group. The SKF model for calculating the frictional moment. AB SKF, 2009. Friction model: rolling, sliding and drag moment components. Verify catalogue edition used for the constants in bearing.py.
- [39] Maksim Smirnov, Natalia Kuklina, Aleksandr Sebelev, Alessandro Zuccato, and Nikolay Zabelin. Comparison of four types of radial turbines for a 250kW ORC power installation. In Proceedings of the 6th International Seminar on ORC Power Systems (ORC2021), Munich, Germany, 2021. Paper ID 63. Verify pages/publisher before final.
- [40] Liam Donnelly. The design and experimental verification of a compact supersonic centripetal impulse turbine. Meng final year project, Imperial College London, Department of Aeronautics, 2025.
- [41] Sydney L. Dixon. Fluid mechanics and thermodynamics of turbomachinery. Butterworth-Heinemann, Boston, Mass. Oxford, 1998.
- [42] Christopher E. Brennen. Hydrodynamics of Pumps. Cambridge University Press, Cambridge, 2011.
- [43] Val S. Lobanoff and Robert R. Ross. Centrifugal Pumps: Design and Application. Gulf Professional Publishing, Houston, 1992.
- [44] Earl Logan Jr. Handbook of Turbomachinery. CRC Press, New York, 1995.
- [45] Ralf H. Stark. Flow separation in rocket nozzles, a simple criteria. Technical Report AIAA 2005-3940, 41st AIAA/ASME/SAE/ASEE Joint Propulsion Conference, Tucson, AZ, 2005.
- [46] Thomas P. Moffitt and Jr. Klag, Frederick W. Experimental investigation of the partial-admission performance characteristics of a single-stage mach 2 supersonic turbine. Technical Report NASA TM X-80, NASA Lewis Research Center, 1959.
- [47] American Petroleum Institute. API standard 521: Pressure-relieving and depressuring systems. American Petroleum Institute, 2014.

A Conventional Impeller Design Attempt

B Supplementary Safety Calculations

The containment and overspeed calculations that sized the protection hardware are in the main body, ?? onwards. This appendix carries the remaining two analyses of the safety case: the venting noise and the venting reaction force. As in the body, the numbers are the 100 bar worst case for the stored air system that was later descoped to 7 bar shop air, retained because the hardware was retained.

B.1 Venting Noise

The sound level of gas venting is estimated per API 521 [47]. The choked mass flow through the vent restriction is

$$\dot{m} = A_{choke} p_0 \frac{\Gamma}{\sqrt{T}}, \quad \Gamma = \sqrt{\frac{\gamma}{R} \left(\frac{2}{\gamma + 1} \right)^{\frac{\gamma+1}{\gamma-1}}} \quad (56)$$

and the sound pressure level at 30 m and at distance r follow from

$$L = 5 \log_{10} \left(\frac{p_0}{p_e} \right) + 51.5, \quad L_{30} = L + 10 \log_{10} \left(\frac{1}{2} \dot{m} a^2 \right), \quad L_p = L_{30} - 20 \log_{10} \left(\frac{r}{30} \right) \quad (57)$$

For the worst case 100 bar vent through a 1/8" line this gives 102 dB at 30 m and 131 dB at 1 m. Against the Control of Noise at Work Regulations 2005 limits, nobody is in the room during venting, and the 27 dB SNR ear defenders worn in the control room bring the exposure below the action level.

B.2 Venting Reaction Force

The reaction force of an open vent is

$$F = \dot{m} a + A (p_{choked} - p_e) \quad (58)$$

with a the speed of sound at the choked condition. At 100 bar a 1/2" vent would produce around 1.6 kN, which is why the vent line is reduced to 1/8", bringing the force to around 100 N against a 50 kg weighted stand, with all vents pointed upward so the reaction acts into the floor.

C Additional Figures and Tables